# FINISH SCHEDULE

| FLOOR | LOCATION: SPACE | | FLOOR: FINISH — Carpet Cork; Vinyl Asbestos; Ceramic Tile; Marble; Terrazzo; Carpeting; Quarry Tile | BASE: Carpet Rubber; Ceramic Tile; Marble; Terrazzo; Quarry Tile; Wood; Vinyl | WALLS: MATERIAL — Masonry or Concrete; Gyp. Plaster on Metal Stud; Metal Stud; Ceramic Tile; Marble; Wood; Special Finish; Plaster | WALLS: FINISH — Unfinished; Painted; Ceramic Tile; Special Finish; Facing Tile; Cast Back; Stone Facing | CEILING: MATERIAL — Metal Pan; Acoustical Tile; Concrete; Sheet Rock; Gyp. Plaster; Luminous Ceil. | CEILING: FINISH — Painted; Unfinished | REMARKS |
|---|---|---|---|---|---|---|---|---|---|
| 4TH FLOOR | ELEV. LOBBY | * | ● | ● | ●● | ● | | ● | * SEE DETAILS OF LOBBY & FINISHES SEE ARCH. DETAILS |
| | TENANT SPACE | * | | | ●● | ● | | ● | * SEE TENANT ARCHITECTS DWG. FOR SUB DIVISION OF SPACE AND FINISHES |
| | CLOSETS | * | ● | ● | ●● | | | ● | * SEE FINAL LOCATION & EXTENT OF CORRIDOR SEE P.A. RENTAL DWGS. |
| | CORRIDOR | * | ● | ● | ●● | ● | ● | ● | * SEE ARCHITECTURAL PLANS FOR EXTENT & TYPE OF SOUNDPROOFING |
| | STAIRS #1, #2, #3, #4 & #5 | * | ● | ● | ●● | | | ● | * SEE ARCHITECTURAL PLANS FOR SOUNDPROOFING |
| | POWDER RM #1 & #2 | * | ● | ● | ●● | ● | ● | ● | * SEE ARCHITECTURAL PLANS FOR SOUNDPROOFING |
| | VEST #1 | * | | ● | ●● | | | ● | * SEE ARCHITECTURAL PLANS FOR SOUNDPROOFING |
| | TEL. CL. 'A', 'B', 'C', 'D', 'E', 'F', 'G' | * | ● | | ●● | ● | ● | ● | * SEE ARCHITECTURAL PLANS FOR SOUNDPROOFING |
| | ELEC. CL. 'A', 'B', 'C', 'D', 'E', 'F', 'G' | * | ● | ● | ●● | | | ● | * SEE ARCHITECTURAL PLANS FOR SOUNDPROOFING |
| | MEN #1 & #2 | * | ● | ● | ●● | ● | ● | ● | * SEE ARCHITECTURAL PLANS FOR SOUNDPROOFING |
| | WOMEN #1 & #2 | * | ● | ● | ●● | | | ● | * SEE ARCHITECTURAL PLANS FOR SOUNDPROOFING |
| | JAN. CL. | * | ● | ● | ●● | ● | ● | ● | * SEE ARCHITECTURAL PLANS FOR SOUNDPROOFING |
| | SERVICE LOBBY | * | ● | ● | ●● | | | ● | * SEE ARCHITECTURAL PLANS FOR SOUNDPROOFING |
| 5TH, 6TH & 7TH FLOORS | TEL. CL. A, B, C, D, E, F, G | * | ● | | ●● | ● | ● | ● | * SEE ARCH. PLAN FOR M.L.P. & VERMICULITE PLASTER, SEE ARCH. |
| | ELEC. CL. 'A', 'B', 'C', 'D', 'E', 'F', 'G' | * | ● | ● | ●● | | | ● | |
| | CLOSETS | * | ● | ● | ●● | ● | ● | ● | |
| | JAN. CL. | * | ● | ● | ●● | | | ● | |
| | VEST #1 & #2 | * | ● | ● | ●● | ● | ● | ● | |
| | TRANSFER PASSAGE | * 6TH & 7TH M.F. | ● | ● | ●● | | | ● | * SEE MECH. PLANS FOR EXTENT AND TYPE OF SOUNDPROOFING. |
| | ELEVATOR ACCESS HALL | * | ● | ● | ●● | ● | ● | ● | |
| | ELEV. LOBBY | * | ● | ● | ●● | ● | | ● | * FOR FINISH OF LOBBY & FINISHES SEE ARCH. DETAIL DRAWINGS |
| | TENANT SPACE | * | ● | ● | ●● | | | ● | * SEE FINAL LOCATION & EXTENT OF CORRIDOR SEE P.A. RENTAL DWGS. |
| | CORRIDOR | * | ● | ● | ●● | ● | ● | ● | * SEE TENANT ARCH. DWGS. FOR SUB-DIVISION OF SPACE & FINISHES. SEE TENANT ARCH. DWGS. FOR SUB-DIVISION OF SPACE & FINISHES. |
| | STAIRS #1, #2, #3, #4 & #5 | * | ● | ● | ●● | | | ● | * SEE MECH. PLANS FOR EXTENT & TYPE OF SOUNDPROOFING |
| | MEN #1, #2, #3, #4 & #5 | * | ● | ● | ●● | ● | ● | ● | * SEE ARCHITECTURAL PLANS FOR SOUNDPROOFING |
| | WOMEN | * | ● | ● | ●● | | | ● | * SEE ARCHITECTURAL PLANS FOR SOUNDPROOFING |
| | MEN'S VEST. #1, #3, #5 | * | ● | ● | ●● | ● | ● | ● | * SEE ARCHITECTURAL PLANS FOR SOUNDPROOFING |
| | POWDER RM. | * | ● | ● | ●● | | | ● | * SEE ARCHITECTURAL PLANS FOR SOUNDPROOFING |
| | TEL. CL. 'A', 'B', 'C', 'D', 'E', 'F' | * | ● | | ●● | ● | ● | ● | |
| | ELEC. CL. 'A', 'B', 'C', 'D', 'E', 'F', 'G' | * | ● | ● | ●● | | | ● | * SEE ARCH PLAN FOR M.L.P. & VERMICULITE PLASTER |
| | JAN. CL. | * | ● | ● | ●● | ● | ● | ● | |
| | SERVICE LOBBY | * | ● | ● | ●● | | | ● | |
| | CLOSETS | * | ● | ● | ●● | ● | ● | ● | * SEE ARCH PLAN FOR M.L.P. & VERMICULITE PLASTER |
| | STORAGE | * | ● | ● | ●● | | | ● | |
| | MAIL ROOM | * | ● | ● | ●● | ● | ● | ● | * SEE ARCHITECTURAL PLANS FOR SOUNDPROOFING |
| | MEN'S VEST #1, #3, #5 | * | ● | ● | ●● | | | ● | |
| | PUBLIC HALL | * | ● | ● | ●● | ● | ● | ● | * SEE TENANT ARCH. DWGS. FOR SUB-DIVISION OF SPACE & FINISHES. |
| | STAIR VEST #3 | * | ● | ● | ●● | | | ● | |
| | COMMODITY TRADING FLOOR | * | ● | ● | ●● | ● | ● | ● | * FOR DETAILS OF LOBBY & FINISHES SEE ARCH. DETAIL DRAWINGS. |
| | ELEVATOR ACCESS HALL | * | ● | ● | ●● | | | ● | |
| 2ND FLOOR | ELEV. LOBBY | * | ● | ● | ●● | ● | ● | ● | * SEE ARCHITECTURAL PLANS FOR SOUNDPROOFING |
| | SERVICE LOBBY | * | ● | ● | ●● | | | ● | * SEE TENANT ARCHITECTS DRAWINGS FOR SUB DIVISION OF SPACE AND FINISHES |
| | MECH. EQUIP. RM. | * | ● | ● | ●● | ● | ● | ● | * SEE MECH. PLANS FOR EXTENT & TYPE |
| | TENANT SPACE | * | | | ●● | | | ● | * SEE FINAL LOCATION & EXTENT OF CORRIDOR SEE P.A. RENTAL DWGS. |
| | STAIRS #1, #2, #3, #4 & #5 | * | ● | ● | ●● | ● | ● | ● | * SEE MECH. PLANS FOR EXTENT & TYPE |
| | VEST #1, #2 & #3 | * | ● | ● | ●● | | | ● | * SEE ARCHITECTURAL PLANS FOR SOUNDPROOFING |
| | MEN #1 | * | ● | ● | ●● | ● | ● | ● | * SEE ARCHITECTURAL PLANS FOR SOUNDPROOFING |
| | WOMEN #1 | * | ● | ● | ●● | | | ● | * SEE ARCHITECTURAL PLANS FOR SOUNDPROOFING |
| | POWDER RM. #1 | * | ● | ● | ●● | ● | ● | ● | * SEE ARCHITECTURAL PLANS FOR SOUNDPROOFING |
| | MEN'S VEST #1 | * | ● | ● | ●● | | | ● | * SEE ARCHITECTURAL PLANS FOR SOUNDPROOFING |
| | FIRE CLOSET | | ● | ● | ●● | ● | ● | ● | |
| | TEL. CL. 'A', 'B', 'D' & 'E' | | ● | ● | ●● | | | ● | |
| | ELEC. CL. 'A', 'B', 'D', 'E', 'F' & 'G' | | ● | ● | ●● | ● | ● | ● | |
| | MEZZANINE PASSAGE | * | ● | ● | ●● | | | ● | |
| | CLOSET | * | ● | ● | ●● | ● | ● | ● | |
| | CORRIDOR | * | ● | ● | ●● | | | ● | |
| | UPPER PORTION OF COMMODITY TRADING FL. | * | ● | ● | ●● | ● | ● | ● | |
| | JAN CL. | | ● | ● | ●● | | | ● | |
| | ELEVATOR ACCESS HALL | * | ● | ● | ●● | ● | ● | ● | |
| MAIN ROOF & BULKHEAD | ELEV. MACH. RM. (PENT'S #3 & #5 THRU 12 SB) | | ● | ● | ●● | ● | ● | ● | * SEE ARCHITECTURAL PLANS FOR EXTENT & TYPE OF SOUNDPROOFING |
| | ELEV. MACH. RM. (PENT'S #1 & #2 #4) | | ● | ● | ●● | | | ● | * SEE ARCHITECTURAL PLANS FOR SOUNDPROOFING |
| | STAIRS #1, #2 & #3 | * | ● | ● | ●● | ● | ● | ● | |
| | VEST. #1, #2 & #3 | * | ● | ● | ●● | | | ● | |
| | MECH EQUIP RM MINIMUM AREA #1 & #2 | | ● | ● | ●● | ● | ● | ● | |

## GENERAL NOTES

1. ALL DIMENSIONS ON DWGS # A-F-1 TO A-F-10 ARE TO ROUGH WALLS AND PARTITIONS
2. ALL DIMENSIONS ON DWG'S A-F-11 TO A-F-16 ARE GIVEN TO FINISH FACE UNLESS SHOWN OR NOTED ACTUAL DIMENSIONS
3. FOR WINDOW HEIGHTS SEE ELEVATIONS AND DETAILS. WINDOW HEIGHTS ARE NOMINAL FOR ACTUAL DIMENSIONS SEE WINDOW CONSTRUCTION DETAILS AND SPECIFICATIONS DRAWINGS.
4. ALL DOORS WITH CLOSERS (OTHER THAN SPRING HINGES) TO BE SET 6" MINIMUM CLEAR OF ADJOINING WALLS ON HINGED SIDE
5. CANTS REQUIRED ON ALL BEAMS PROJECTIONS OVER 8" NOMINAL (ACTUAL) DIMENSION IN ELEVATION SHAFTS AND SHALL BE MINIMUM 12" FROM HORIZONTAL BUT TYPICAL REFER TO ARCHITECTURAL DRAWINGS
6. FOR PRIMARY A.C. UNITS AIR CONDITIONING DUCT WORK, PIPING & EQUIPMENT AND FOR EXHAUST DUCTS ETC. SEE MECHANICAL DWGS.
7. FOR ALL PLUMBING PIPES, RISERS, DRAINAGE AND DETAILS ETC. SEE PLUMBING DWGS.
8. FOR ALL ELECTRICAL WIRING RISER DIAGRAMS, LIGHTING, CONVENIENCE OUTLETS AND DETAILS SEE ELECTRICAL DWGS.
9. ALL TRENCH WORK SHALL BE PERFORMED TO UNDERSIDE OF SLAB AND WIDTH OF TRENCH SHALL BE AS SHOWN ON TYPE OF FIREPROOFING SEE ARCHITECTURAL SPECIFICATIONS FOR TYPE AND EXTENT OF TRENCH HEADER AND FIREPROOFING
10. WHERE NO SUSPENDED CEILING IS CALLED FOR, EACH ARE IN CLOSETS, STAIR PASSAGE ETC. BOTTOM ELEVATION OF ALL PIPING AND DUCT WORK SHALL BE MAINTAINED AT 7'-10" MINIMUM ABOVE FINISH FLOOR TO PROVIDE FOR FUTURE CEILING INSTALLATION AND CLEARANCE OF FULL HEIGHT DOORS.
11. WHERE CLOSE BEAM FIREPROOFING IS CALLED FOR AROUND COLUMNS CINDER BLOCK SHALL BE USED UNLESS OTHERWISE NOTED.
12. ALL ELECTRIC CALLS, PANELS AND TELEPHONE TYPE ARE LOCATED OVER ELEVATOR MACHINE ROOMS, CLOSETS, SHAFTS AND STAIRWAYS THEY ARE INDICATED ON FLOOR PLANS BY LETTERS WITH A SYMBOL ON TYPE OF FIREPROOFING SEE ARCHITECTURAL SPECIFICATIONS FOR TYPE AND EXTENT OF ELECTRIC CALLS AND FIREPROOFING
13. ALL SLABS OUTSIDE OF BUILDING PERIMETER AT STREET LEVEL SHALL HAVE WATERPROOFING AND INSULATION IN ACCORDANCE WITH DETAILS SHOWN ON DWG #A-F-3.1 & A-F-3.2
14. ALL WALLS AND PARTITIONS SHOWN WITH DASHLINE ARE INCLUDED IN THIS CONTRACT ALL WORK WITHIN HEAVY BORDER LINES AND SHOWN UNSHADED IS IN A SEPARATE CONTRACT ALL OTHER WORK SHOWN SHADED OR OTHERWISE IS NOT INCLUDED IN THIS CONTRACT CONTRACTORS SHALL CAREFULLY INVESTIGATE AND FAMILIARIZE THEMSELVES WITH EXISTING CONDITIONS AND DIMENSIONS
15. SLAB OVER ALL SLOTS IN ELECTRICAL & TELEPHONE CLOSETS AFTER LAYOUTS ARE IN PLACE

2

## ABBREVIATIONS, SYMBOLS & KEY TO MATERIALS

| | | | |
|---|---|---|---|
| A.C. | AIR CONDITIONING | LAV. | LAVATORY |
| A.C. | ACOUSTIC | L/P | LOW POINT |
| A.D. | ACCESS DOOR | | |
| ALUM. | ALUMINUM | MACH. | MACHINE |
| | | MAX. | MAXIMUM |
| BL. | BLOCK | MEMB. | MEMBRANE |
| BM. | BEAM | MIN. | MINIMUM |
| BOT. | BOTTOM | ML. | METAL LATH |
| BLDG. | BUILDING | ML.F. | METAL LATH FURRING |
| BD. | BOARD | M.O. | MASONRY OPENING |
| B.R. | BOTTOM REGISTER | M.R. | MOP RECEPTOR |
| | | MECH. | MECHANICAL |
| CEM. | CEMENT | M.S. | MARBLE SADDLE |
| ℄ | CENTER LINE | MET. | METAL |
| CL. | CLOSET | | |
| CEIL. | CEILING | N/C. | NOT IN CONTRACT |
| C.E. | COMBINATION ELEVATOR | N.T.S. | NOT TO SCALE |
| COL. | COLUMN | NO. | NUMBER |
| CONC. | CONCRETE | | |
| COND. | CONDUIT | O.C. | ON CENTER |
| CONST. | CONSTRUCTION | OPNG. | OPENING |
| CONT. | CONTINUOUS | OPP. | OPPOSITE |
| C.T. | CERAMIC TILE | OD. | OUTSIDE DIAMETER OR DIMENSION |
| CTR. | CENTER | | |
| CAST. | CABINET | | |
| CONTR. | CONTRACTOR OR CONTRACT | PA. | PORT AUTHORITY |
| C.B. | COMBINATION SUPERVISOR | PARTN. | PARTITION |
| | | PE. | PASSENGER ELEVATOR |
| DET. | DETAIL | P.H. | PAPER HOLDER |
| D.F. | DRINKING FOUNTAIN | PL. | PLATE |
| DN. | DOWN | PLAS. | PLASTER |
| DWG. | DRAWING | PTD. | PAINTED |
| DIA. ○ | DIAMETER | POL. | POLISHED |
| DR. | DOOR | | |
| | | Q.T. | QUARRY TILE |
| EL. | ELEVATION | | |
| ELEC. | ELECTRICAL | R. | RISER |
| ELEV. | ELEVATOR | RAD. | RADIUS |
| ESC. | ESCALATOR | R.D. | ROOF DRAIN |
| EQ. | EQUAL | RM. | ROOM |
| EQUIP. | EQUIPMENT | REF. | REFRIGERATION |
| EXP. | EXPOSED | R.S. | RESILIENT SADDLE |
| EXPAN. JT. | EXPANSION JOINT | R.T. | RESILIENT |
| EXTR. | EXTRUDED OR EXTRUSION | REINF. | REINFORCED OR REINFORCEMENT |
| EXT. | EXTERIOR | REQ'D. | REQUIRED |
| F.A.I. | FRESH AIR INTAKE | S.A. | SUPPLY AIR |
| F.H.C. | FIRE HOSE CABINET | S.E. | SERVICE ELEVATOR |
| FIN. | FINISH | SEC. | SECTION |
| FL. | FLOOR | SIM. | SIMILAR |
| F.P. | FIREPROOFING | S.N.D. | SANITARY NAPKIN DISPENSER |
| F.P.S.C. | FIREPROOF SELF CLOSING | S.N.V. | SANITARY NAPKIN VENDOR |
| F.T. | FACING TILE | S.S. | SERVICE SINK |
| F.E. | FREIGHT ELEVATOR | ST. STL. | STAINLESS STEEL |
| F.D. | FLOOR DRAIN | STL. | STEEL |
| FXT. | FIXTURE | SUSP. | SUSPENDED |
| GYP. | GYPSUM | T.C.R. | TOWEL CABINET & RECEPTACLE |
| GL. | GLASS | T.E. | TOILET EXHAUST |
| HORIZ. | HORIZONTAL | TEL. | TELEPHONE |
| H. | HIGH | T.R. | TOP REGISTER |
| HT. | HEIGHT | TYP. | TYPICAL |
| H.P. | HIGH POINT | T.&B.R. | TOP & BOTTOM REGISTER |
| H.M. | HOLLOW METAL | T. | TREAD |
| HR. | HOUR | T.D. | TIE DOWN |
| H.R. | HAND RAIL | | |
| H.V.A.C. | HEATING, VENTILATING & AIR CONDITIONING | V.A.T. | VINYL ASBESTOS TILE |
| | | VEST. | VESTIBULE |
| I.D. | INSIDE DIAMETER OR DIMENSION | V.T. | VINYL TILE |
| INT. | INTERIOR | V.W.C. | VINYL WALL COVERING |
| INSUL. | INSULATION | VERT. | VERTICAL |
| JT. | JOINT | W.D. | WOOD |
| JAN. CL. | JANITOR'S CLOSET | W.P. | WATERPROOFING |
| | | W.P. | WORKING POINT |
| K.E. | KITCHEN EXHAUST | W. | WIDE OR WIDTH |

RECEIVED
FEB 28 1975
SKILLING - HELLE
CHRISTIANSEN - ROBERTSON
230 PARK AVE, N.Y.C.

CONTRACT BID DRAWING date 11-21-73

| NO. | DATE | REVISIONS | NO. | DATE | REVISIONS |
|---|---|---|---|---|---|
| | | | 2 | 7-17-74 | REV #1 |
| | | | 1 | 12-19-73 | ADD #1 |

APPROVED
CHIEF, PLANNING DIVISION
DATE

REGISTERED ARCHITECT

THE WORLD TRADE CENTER
THE PORT AUTHORITY OF NEW YORK AND NEW JERSEY

MINORU YAMASAKI & ASSOCIATES
MINORU YAMASAKI, ARCHITECT

SKILLING, HELLE, CHRISTIANSEN, ROBERTSON
STRUCTURAL ENGINEERS

EMERY ROTH & SONS
RICHARD ROTH, ARCHITECT

THE PORT AUTHORITY OF NEW YORK AND NEW JERSEY
MECHANICAL, ELECTRICAL, PAVING, UTILITIES, FOUNDATIONS

TITLE: SOUTHEAST PLAZA BUILDING
FINISH SCHEDULE

| | | | |
|---|---|---|---|
| DRAWN | | CHECKED | |
| SCALE | | DATE | 11-15-73 |
| PROJECT NUMBER | | SHEET | OF |
| DRAWING NUMBER | A-F-4 | | |