NORTH

MATCH LINE
FOR CONTINUATION OF PLAN
SEE DRAWING # A-F1.57

S.A.R.A. SHAFT
ELEC. CL. B
TEL CL. B
PIPE SPACE
ELEC. CL. A
TEL CL. A
ELEC. CL. C
TEL CL. C
ELEVATOR LOBBY
WOMEN #1
MEN #1
POWDER ROOM
ELEC. CL. D
TEL CL. D
TE & PIPE SHAFT
ELEC. CL. F
TEL CL. F
S.A.R.A. SHAFT
PIPE SHAFT
SEE DETAIL THIS DRG.
PUBLIC CORRIDOR CLOSURE PARTITIONS ABOVE SUSPENDED CEILING. SEE DETAILS ON DRAWG. A-F.124
TENANT SPACE
TO SPACES @ 9'-5" = 175'-0"
181'-6"

Notes

1. FOR GENERAL NOTES, KEY TO MATERIALS, ABBREVIATIONS, FINISH SCHEDULE, DOOR SCHEDULE, SYMBOLS OF DRAWINGS, SEE DRAWINGS "A-F.1 TO A-F.5
2. FOR COMPLETE 5TH SCALE CORE PLAN SEE DRAWING # A-F.57
3. ALL ELEVATIONS INDICATED THUS (+0'-0") ARE TAKEN IN RELATION TO FINISH FLOOR
4. FOR ALL MECHANICAL & ELECTRICAL LAYOUTS, SEE RESPECTIVE ENGINEERS DRAWINGS
5. FOR TYPICAL STAIR DETAILS, SEE DRAWING # A-F.100
6. FOR TYPICAL TOILET DETAILS SEE DRAWINGS "A-F.101
7. ALL TRENCH HEADERS TO BE FIREPROOFED AT UNDERSIDE OF SLAB FOR A WIDTH OF 4'-0 WITH A SPRAY-ON FIREPROOFING. SEE ARCHITECTURAL SPECIFICATIONS FOR TYPE AND ELECTRICAL ENGINEERS & CONTRACTORS APPROVED SHOP DRAWINGS FOR LOCATION & EXTENT OF TRENCH HEADERS & FIREPROOFING.
8. FINISHED FLOOR ELEVATION AND TOP OF SLAB ELEVATION ARE (+0'-0") UNLESS OTHERWISE SHOWN OR NOTED.
9. CAMTS ARE REQUIRED ON ALL BEAM PROJECTIONS OVER 9" ACTUAL DIMENSION IN ELEVATOR SHAFTS AND SHALL BE MINIMUM 75° FROM HORIZONTAL. SEE TYPICAL DETAILS ON DRG. "A-F.134
10. FOR CORRIDOR AND TOILET LIGHTING LAYOUTS, SEE DRG. "A-T.61. FOR ALL OTHER LIGHTING, SEE ELECTRICAL DRAWINGS AND ARCHITECTURAL DETAILS.
11. CUTS AND SUB-DIVISION OF TENANT SPACE TO BE DETERMINED FROM TENANT ARCHITECTS DRAWINGS.
12. FOR FIREPROOFING OF ALL FREE STANDING COLUMNS WITHIN PERIMETER WALL NOT SHOWN OR NOTED ON THIS PLAN OR ON CORE PLANS. PROVIDE SPRAY-ON FIREPROOFING AROUND COLUMNS AND FINISH WITH METAL STUDS & ½" GYPSUM WALLBOARD. SEE TYPICAL DETAILS ON DRAWINGS "A-F.124.
13. EXTERIOR WALL DIMENSIONS ARE TO BE USED ONLY FOR NUMBER OF WINDOW SPACES, FOR SIZE OF MULLIONS AND OVERALL DIMENSIONS, SEE DETAIL DRAWINGS.

PIPE SHAFT DETAILS
SCALE 1/4" = 1'-0"

NOTE: SEAL PIPE SHAFT AFTER PIPES ARE PLACED

PLAZA
SIXTH LINE
FIFTH LINE
CHURCH STREET
LIBERTY STREET

KEY PLAN

CONTRACT BID DRAWING date 11-21-73

NO.	DATE	BUL. NO.	BY	NO.	DATE	BUL. NO.	BY
				1	12-19-73	400-1	L.J.

REVISIONS

APPROVED

CHIEF, PLANNING DIVISION
DATE

RECEIVED
FEB 28 1975

THE WORLD TRADE CENTER

THE PORT AUTHORITY OF NEW YORK AND NEW JERSEY

MINORU YAMASAKI & ASSOCIATES
MINORU YAMASAKI, ARCHITECT

EMERY ROTH & SONS
RICHARD ROTH, ARCHITECT

SKILLING, HELLE, CHRISTIANSEN, ROBERTSON
STRUCTURAL ENGINEERS

THE PORT AUTHORITY OF NEW YORK AND NEW JERSEY
MECHANICAL, ELECTRICAL, PAVING, UTILITIES, FOUNDATIONS

TITLE: SOUTHEAST PLAZA BUILDING
5TH FLOOR PLAN
SOUTH SECTION

DRAWN		CHECKED	
SCALE	1/4"-1'-0"	DATE	11-15-73
PROJECT NUMBER		SHEET	OF
DRAWING NUMBER	A-F.56		