NORTH

HIGH FLOOR OF LOWER ROOF EL. 131.5

MATCH LINE

TENANT SPACE WITH SLOPED TOP OF SLAB EL. 131.5 ABOVE

UPPER PORTION OF COMMODITY TRADING FLOOR

MECHANICAL EQUIPMENT ROOM FINISH FLOOR TOP OF SLAB EL. 131.5

CONC. PADS FOR DETAILS SEE MECH. DWGS.

NOTES:

1. FOR GENERAL NOTES, LEGEND, SYMBOLS, ABBREVIATIONS, FINISH SCHEDULE, DOOR SCHEDULE & DETAILS SEE DRAWING # A-1-01.
2. FOR COMPLETE KEY SCALE CORE PLAN SEE DRAWING # A-1-01.
3. ALL DIMENSIONS INDICATED THUS (N.O.P.) ARE TAKEN IN RELATION TO FINISH FLOOR.
4. FOR ALL MECHANICAL & ELECTRICAL LAYOUTS SEE RESPECTIVE ENGINEERING DRAWINGS.
5. FOR TYPICAL JOINT DETAILS SEE DRAWING # A-1-100.
6. FOR TYPICAL TOILET DETAILS SEE DRAWING # A-1-101.
7. ALL TENANT IMPROVEMENTS TO BE PERFORMED AT EXPENSE OF SUB-LET AS PART OF SUB-LET AGREEMENT & CONSTRUCTION TO BE COORDINATED WITH GENERAL CONTRACTOR & SUBJECT TO APPROVAL BY THE PORT AUTHORITY OF NEW YORK & NEW JERSEY.
8. FINISHED FLOOR ELEVATION AND TOP OF SLAB ELEVATION ARE 12-0" UNLESS SHOWN OR NOTED.
9. SLOPE ALL FLOOR TO DRAIN WHERE INDICATED. SLOPE FLOOR SMOOTHLY BETWEEN DRAINS WHERE NOT INDICATED.
10. FOR FURNITURE, TOILET, EXITING LAYOUTS SEE ARCH. PLAN. FOR ALL OTHER LIGHTING, SEE ELECTRICAL DRAWINGS & SPECIFICATIONS.
11. 3" EXITS AND DUMBWAITER OPENINGS TO BE WITHDRAWN FROM TENANTS ARCHITECTS WORK.
12. FOR DIMENSIONS OF SMOKE PARTITIONS COVERING, INSTALLATIONS TO BE WELL WET, SEALING OF JOINTS AT FLOOR, CEILING & WALLS, PENETRATIONS & OPENINGS IN SMOKE PARTITIONS & DOORS IN SMOKE PARTITIONS WITH METAL SILLS & OPENING WELDED SEE TYPICAL DETAILS ON DRAWING NO. A-1-100.
13. EXTERIOR WALL DIMENSIONS ARE TO BE USED ONLY FOR PURPOSES OF SHOWING SPACES & FOR SIZE OF ENCLOSING ALIGNMENT ALL DIMENSIONS SEE DETAIL DRAWINGS.
14. ALL DOORS MARKED THUS (X) ARE 3'-0" X 7'-0" HIGH INCLUDING FRAME AND ARE TO BE FURNISHED COMPLETE WITH ALL HARDWARE & FRAME BY THE PORT AUTHORITY OF NY. & N.J. AND INSTALLED BY BASE BUILDING CONTRACTOR. ALL DOORS TO BE F.R.P. & E.I. WITH FULL PANIC HARDWARE.

RECEIVED
DEC 8 1983

ROBERTSON, FOWLER & ASSOCIATES P.C.
211 EAST 49TH ST., N.Y.C. 10017

KEY PLAN

PLAZA
MATCH LINE
LIBERTY STREET
CHURCH STREET

EXISTG. CONC. CURB
EXISTG. NET. STOD & STY. SD. WALL
3'C & NET. FORMING BRACKETS @ 5'-0" O.C. & FORMING 1'S 24'0" C. 4" STY. SD. UP TO CLG.
REMOVE EXIST'G FILL & REMAINING V.P. SCREED SLAB AND APPLY SKORING COMPOUND REMOVED POURING CURB
NEW NET. STUD & 5/8" STY. SD. WALL
NEW CONC. CURB
ADD W.P. AT CURB & STRIP INTO EXIST'G. W.P. MEMBRANE
REPLACE FILL

A-A SECTION AT EXISTING & NEW CONCRETE CURBS
SCALE: 1/4"=1'-0"

CONTRACT - BID-DRAWING - date: 11-21-75

NO.	DATE	REVISIONS	BY
A	6-27-77	R-78	A.C.
A	10-27-77	R-27	K.W.
A	1-10-77	R-45	E.M.
A		E-7	L.J.
A	10-20-76	F-0	L.J.
A	2-10-76	F-5	C.G.
A	10-17-75	F-8	C.G.
A	7-7-76	REV.	J.L.
A	12-19-75	ADD'L	J.L.

APPROVED
CHIEF, PLANNING DIVISION
DATE

THE WORLD TRADE CENTER

THE PORT AUTHORITY OF NEW YORK AND NEW JERSEY

MINORU YAMASAKI & ASSOCIATES
MINORU YAMASAKI, ARCHITECT

SKILLING, HELLE, CHRISTIANSEN, ROBERTSON
STRUCTURAL ENGINEERS

EMERY ROTH & SONS
RICHARD ROTH, ARCHITECT

THE PORT AUTHORITY OF NEW YORK AND NEW JERSEY
MECHANICAL, ELECTRICAL, PAVING, UTILITIES, FOUNDATIONS

TITLE: SOUTHEAST PLAZA BUILDING 9TH FLOOR PLAN
SOUTH SECTION

DRAWN	CHECKED
SCALE	1/8"=1'-0"
DATE	8-15-75
PROJECT NUMBER	
SHEET	OF
DRAWING NUMBER	A-F-88