No.	REVISIONS	—
7/30/84	SUBMITTED TO PORT AUTH. AUTH. FOR REVIEW	
8/8/84	SUBMITTED TO PORT AUTHORITY FOR REVIEW	
10/8/84	SUBMITTED TO P.A. FOR REVIEW	

NOTE: EXIST. TOILET PARTITIONS, DOORS, PLANTERS, BKTS., HARDWARE, ACCESSORIES, TOILETS, ETC. TO REMAIN UNLESS OTHERWISE NOTED

REMOVE EXIST. SANITARY NAPKIN DISPENSERS & WASTE RECEPTACLES AND TAMPON DISPENSER & RELOCATE AS SHOWN IN CONSTRUCTION PLAN 2/1-A-11

REMOVE ALL EXIST. C.O., SURFACE(S) SYSTEM, ETC. @ EXIST. LADIES TOILETS

REMOVE EXIST. CER. TILE & SETTING BED AT ALL AREAS AS INDICATED (TYP.) TO ALLOW FOR NEW CONSTRUCTION

FOR DEMOLITION OF THIS AREA SEE DWG# 1-A-1

REMOVE EXIST. OLD PLANTER & PROVIDE NEW - SEE CONSTRUCTION PLAN 2/1-A-11.

REMOVE EXIST. MIRROR & SHELF

REMOVE EXIST. SINKS, FAUCETS, AND SOAP DISPENSERS AND RELOCATE AS SHOWN IN CONSTRUCTION PLAN 2/1-A-11.

PROVIDE NEW SETTING BED & CERAMIC TILE TO MATCH EXIST. IN ALL AREAS AS INDICATED (TYP.)

REMOVE EXIST. TOILETS & SHELF & SEATS

NOTE: ALL NEW PARTITIONS SHALL REST ON EXIST. FLOOR SLAB (TYP.) UNLESS OTHERWISE NOTED. REMOVE EXIST. CER. TILE & MORTAR BED AS REQ'D TO ACCOMODATE TILE & PANEL REPAIR & REINSTALL (CER. TILE) AND/OR PROVIDE NEW CER. TILE & MORTAR BED AROUND PARTITIONS AS REQ'D TO MATCH EXIST. ADJACENT FLOOR. AREAS INDICATED ON DWG. FOR TILE & BED REMOVAL AS WELL AS PATCHING W/ NEW ARE DIAGRAMMATIC & SHALL BE FIELD VERIFIED & ALL DISCREPANCIES REPORTED TO ARCHITECT PRIOR TO SUBMITTING BID (SEE SPECIFICATIONS).

1 DEMOLITION PLAN
SCALE: 1/4"=1'-0"

PROVIDE NEW TOILET PARTITIONS, DOORS, PLANTERS, BRACKET, HARDWARE ACCESSORIES, TOILET FLUSH VALVES, SEATS, ETC. TO MATCH EXIST. (TYP.)

THIS EXIST. WALL PROVIDE ONE LAYER OF 5/8" G.W.B. FOR FUR TO SLAB & SOUND PROOFING TO MATCH EXIST. (TYP.)

EXIST. TOILET PARTITIONS, DOORS, PLANTERS, BKTS., HARDWARE ACCESSORIES, TOILETS, ETC. TO REMAIN

RELOCATE EXIST. SINKS, FAUCETS & SOAP DISPENSERS AS SHOWN. PROVIDE TWO NEW SINKS, ETC. TO MATCH.

NEW COUNTER & MIRROR SEE DETAIL 4/1-A-11.

FOR CONSTRUCTION OF THIS AREA SEE DWG# 1-A-1

LADIES TOILETS

2 CONSTRUCTION PLAN
SCALE: 1/4"=1'-0"

E.L.O. HT. 10'-11" A.F.F. (V.I.F. EXIST.)

PLANTERS @ C.L.G. DETAIL OF C.L.G. PENETRATIONS & NEW PLANTER CABLE CUTS TO MATCH EXISTING SYSTEMS TO MATCH EXIST. (TYP.)

PROVIDE ALL NEW CEILING SUSPENSION SYSTEM, ETC. TO MATCH EXIST. (TYP.)

3 REFLECTED CEILING PLAN
SCALE: 1/4"=1'-0"

EXIST. TOILET CONSTRUCTION

NEW TOILET CONSTRUCTION

NOTE: ALL RELOCATED TOILET FIXTURES & ACCESSORIES AS WELL AS NEW SHALL HAVE MOUNTING HEIGHTS TO MATCH EXIST. UNLESS OTHERWISE LISTED (TYP.).

A ELEVATION
SCALE: 1/4"=1'-0"

NEW TOILET PARTITIONS

NEW TOILET PAPER DISPENSER

NEW TOILET

NEW SANITARY NAPKIN DISPOSAL

RELOCATED EXIST. SOAP DISPENSERS (TYP. AS WALL)

RELOCATED EXIST. PAPER TOWEL DISPENSER & WASTE RECEPTACLE W/ NEW SURFACE MTD. STAINLESS STL. SHIM (COMPATIBLE W/ EXIST. DESIGN & FINISH.)

RELOCATED EXIST. SINKS & FAUCETS. PROVIDE NEW TRAPS, PLUMBING, CONNECTIONS, PIPING, ETC. - TYP. FOR ALL NEW & EXIST. RELOCATED.

B ELEVATION
SCALE: 1/4"=1'-0"

NEW SOAP DISPENSER TO MATCH EXIST. PROVIDE TWO(2)

NEW SINK & FAUCET TO MATCH EXIST. PROVIDE TWO(2)

NEW MIRROR

NEW COUNTER

C ELEVATION
SCALE: 1/4"=1'-0"

CAULK WOOD BLOCKING

SUSPENDED C.G.

WOOD CLEATS

1/4" POLISH PLATE GLASS MIRROR ON MASTIC ON 1/2" PLYWOOD BACKING

1/8"x7/8" POLISHED ALUMINUM TRIM (4 SIDES)

1/8" SEALANT (COLOR TO MATCH GROUT IN CERAMIC TILE)

MAS. LAM. TOP & BACKSPLASH

CAULK 1/8" x 1/8" EXP. ALUM. STRIP (3 SIDES)

CAULK W.D. BLOCKING

FINISH CERAMIC TILE FLOOR

EXIST. CONC. SLAB

NOTE: MATCH EXIST. SETTING BED & WALLS & FLOORS - TYP. (V.I.F.)

4 DETAIL
SCALE: 3"=1'-0"

SHELF BELOW

1/8"x7/8" ALUM. TRIM

LINE OF GYP. BD. PARTITION

3/4"

5 DETAIL
SCALE: 3"=1'-0"

RELOCATED EXIST. SOAP DISPENSERS PAPER & SINKS

NEW SOAP DISPENSERS, PAPER & SINKS TO MATCH EXIST.

NEW TOILET PARTITIONS

NEW TOILET PAPER DISPENSER

NEW TOILET

NEW SANITARY NAPKIN DISPOSAL

D ELEVATION
SCALE: 1/4"=1'-0"

CEC
COMMODITIES EXCHANGE CENTER, INC.
FOUR WORLD TRADE CENTER
NEW YORK, NEW YORK 10048

PHASE 1
EGRESS UPGRADE
AREA C

dwg. title:
LADIES TOILETS

SIMONENDRE BRIGNATI & MAZZOTTA, P.C. ARCHITECTS
270 SEVENTH AVENUE NEW YORK, NEW YORK 10001 (212) 886-9800

project 1930
scale AS NOTED
date 9/7/84

dwg. no.
1-A-13