date	REVISIONS	
12/21/04	SUBMITTED TO DOT AUTHORITY FOR REVIEW	
4/7/04	REVISED TO COMPLY WITH P.A. COMMENTS	2
6/9/04	SUBMITTED TO DOT AUTHORITY FOR REVIEW & GENERAL REVISIONS	2
11/10/04	SUBMITTED TO P.A. FOR REVIEW	

1 PART CONSTRUCTION / DEMOLITION PLAN (8TH FLOOR) NOTE: FOR ADDITIONAL NOTES (CONST. & DEMO) SEE 2, 3, 4/1-A-9

2 PART REFLECTED CEILING PLAN (8TH FLOOR)

3 PART OCCUPANCY PLAN (8TH FLOOR)

4 PART FINISH PLAN (8TH FLOOR)

5 PART CONSTRUCTION/DEMOLITION PLAN (8TH FL.)

6 PART REFLECTED CEIL. PLAN (8TH FLOOR)

7 PART CONSTRUCTION / DEMO / FIN. PLAN (7TH FLOOR)

NOTE #1: REMOVE EXISTING VINYL BASE, CEILING, PLASTIC ETC. FROM EXISTING 1-HR. RATED CORRIDOR OR ENCLOSURE TEMPORARY PARTITION (V.I.F.) WITH DESIGNATION ( ) UPGRADE TO 2-HR. BY PROVIDING EXPOSED SIDE W/ LAYER OF GYP. BD. (FURRING "C") OR EACH SIDE FOR FULL HT. OF PARTITION. PROVIDE NEW VINYL BASE TO MATCH EXISTING (SEE DET'S 5, 6, 7, 8 & 9/A-22). ALL EXISTING WALL MOUNTED SWITCHES, OUTLETS, WALL FIXTURES, ETC. AFFECTED BY CONSTRUCTION SHALL BE RELOCATED TO NEW WALL FLUSH AS REQ'D TO MATCH ADJACENT EXISTING CONDITION. CONTRACTOR SHALL SURVEY ALL SUCH CONDITIONS BEFORE SUBMITTING BIDS (TYP.).

8 PART REFLECTED CEILING PLAN (7TH FLOOR)

NOTE: FOR CLG. WORK THIS AREA, SEE NOTE #2 DWG #A-9.

9 PART CONSTRUCTION / DEMOLITION / FINISH PLAN (7TH FLOOR)

NOTE #2: REMOVE EXISTING CEILING SUSPENSION SYSTEM AND LIGHTS AS REQ'D TO ALLOW FOR NEW 2-HR. CONSTRUCTION AND UPGRADING OF EXISTING PARTITIONS. PROVIDE NEW CEILING AND SUSP. SYSTEM TO MATCH EXISTING FOR FIXTURES REMOVED. SIDEWALL LIGHTS MARKED "R" (RELOCATED) OR FLUSH (TYP.) TO LOCATIONS SHOWN. FOR MECH., ELEC., SPRINKLER, & PLUMBING WORK AND RELOCATIONS, SEE RESPECTIVE DRAWINGS.

NOTE #3: THE ATTACHMENT OF ADDITIONAL GYPSUM WALLBOARD PANELS TO EXISTING WALLS REQUIRING INCREASED FIRE RESISTANCE RATING SHALL BE IN ACCORDANCE WITH THE CONSTRUCTION METHODS OF SIMILAR RCA APPROVED WALLS, AND/OR IN ACCORDANCE WITH ESTABLISHED P.A. STANDARDS.

10 PART REFLECTED CEILING PLAN (7TH FLOOR)

NOTE: FOR CLG. WORK THIS AREA, SEE NOTE #2, DWG. #A-9.

CEC
COMMODITIES EXCHANGE CENTER, INC.
FOUR WORLD TRADE CENTER
NEW YORK, NEW YORK 10048

EGRESS UPGRADE
PHASE 1 AREA F&J

dwg title:
7TH & 8TH FLOORS
PART PLANS

SCHNEIDER GRISANTI & MAZZOTTA, P.C. ARCHITECTS
270 SEVENTH AVENUE NEW YORK, NEW YORK 10001 (212) 255-8000

project 1999
scale AS NOTED
date 2/21/04

dwg no. 1-A-9