DOOR SCHEDULE

Door No.	Type	No. Leafs	DOOR Material	DOOR Width	DOOR Height	DOOR Thickness	DOOR Label	DOOR Undercut	FRAME Jamb Type	FRAME Head Type	FRAME Material	FRAME Saddle Type	FRAME Reinforcement	HARDWARE	REMARKS
101	A	1	HM	3'-0"	7'-0"	1¾"	D	—	2	2	HM	—	YES	3, 4, 7, 12	
102	A	1	HM	3'-0"	7'-0"	1¾"	D	—	2	2	HM	—	YES	3, 4, 7, 12	
203	EXISTING DOOR ASSEMBLY RELOCATED														
301	A	1	HM	4'-0"	7'-0"	1¾"	B	3/4"	2	2	HM	5-1	YES	1, 4, 7, 10, 12	
302	A	1	HM	3'-0"	7'-0"	1¾"	B	—	2	2	HM	5-3	YES	1, 4, 7, 12, 10	
401	A	1	HM	4'-0"	7'-0"	1¾"	B	3/4"	2	2	HM	5-1	YES	1, 4, 7, 10, 12	
402	A	1	HM	3'-0"	7'-0"	1¾"	B	—	2	2	HM	5-3	YES	1, 4, 7, 12, 10	
501	A	1	HM	4'-0"	7'-0"	1¾"	B	3/4"	2	2	HM	—	YES	1, 4, 7, 10, 12	
502	A	1	HM	3'-0"	7'-0"	1¾"	B	—	2	2	HM	5-3	YES	1, 4, 7, 12, 10	
601	A	1	HM	4'-0"	7'-0"	1¾"	B	3/4"	2	2	HM	—	YES	1, 4, 7, 10, 12	
602	A	1	HM	3'-0"	7'-0"	1¾"	B	—	2	2	HM	5-3	YES	1, 4, 7, 12, 10	
701	A	1	HM	4'-0"	7'-0"	1¾"	B	3/4"	2	2	HM	—	YES	1, 4, 7, 10, 12	
702	A	1	HM	3'-0"	7'-0"	1¾"	B	—	2	2	HM	5-3	YES	1, 4, 7, 12, 10	
703	EXISTING DOOR ASSEMBLY RELOCATED														
704	EXISTING DOOR ASSEMBLY RELOCATED														
705	A	1	HM	3'-0"	7'-0"	1¾"	C	3/4"	5	5	HM	—	YES	1, 4, 7, 12	RELOCATED CARPENTRY SHELVES (SEE PLANS)
706	A	1	HM	3'-0"	7'-0"	1¾"	B	—	2	2	HM	—		1, 4, 7, 12 DELETED	
707	A	1	HM	3'-0"	6'-8"	1¾"	C	3/4"	5	5	HM	5-1	YES	1, 4, 7, 12	RELOCATED CARPENTRY SHELVES (SEE PLANS)
708	B	2	HM	6'-0"	7'-0"	1¾"	—	3/4"	3	4	HM	5-4	YES	7, 8, 9	
709	B	2	HM	6'-0"	7'-0"	1¾"	—	3/4"	3	4	HM	5-4	YES	7, 8, 9	
710	A	1	HM	2'-0"	7'-0"	1¾"	—	3/4"	1	1	HM	5-4	—	3, 8, 7	
711	DOOR AND HARDWARE SALVAGED														
712	A	1	HM	3'-0"	7'-0"	1¾"	B	—	11	11	HM	—	—	1, 4, 7, 12, 13, 18	ALARM WIRED TO ALL BOTH FIRE SYSTEM
713	B	2	HM	6'-0"	7'-0"	1¾"	B	—	8	9	HM	—	—	7, 12, 16, 19	DOOR TO FREE SPACE, WIRED TO ALL DOOR WITH ACTUATOR AT DOOR ALARM, MONITORED
714	B	2	HM	6'-0"	7'-0"	1¾"	B	—	8	9	HM	—	—	7, 12, 16, 19	
801	DOOR AND HARDWARE SALVAGED														
802	DOOR AND HARDWARE SALVAGED														
803	DOOR AND HARDWARE SALVAGED														
804	A	1	HM	3'-0"	7'-0"	1¾"	B	—	2	2	HM	5-1	YES	1, 4, 7, 11, 12, 14	
805	A	1	HM	2'-0"	7'-0"	1¾"	B	—	2	10	HM	5-1	YES	1, 4, 7, 11, 14	
806	A	1	HM	2'-0"	7'-0"	1¾"	B	3/4"	1	7	HM	5-1	YES	1, 5, 6, 7, 8	
807	DOOR AND HARDWARE SALVAGED														
808	A	1	HM	3'-0"	7'-0"	1¾"	B	3/4"	13	14	HM	5-1	YES	3, 4, 5, 7, 11, 18, 19	RELOCATE EXIST. HOLLOW METAL FRAME & DOOR, PATCH & PAINT AS REQUIRED
809	A	1	HM	3'-0"	7'-0"	1¾"	B	3/4"	12	12	HM	5-1	YES	1, 4, 6, 7, 11	
810	A	1	HM	3'-0"	7'-0"	1¾"	—	3/4"	2	6	HM	5-8	YES	1, 4, 5, 7	
811	A	1	HM	3'-0"	7'-0"	1¾"	—	3/4"	2	6	HM	5-8	YES	1, 4, 5, 7	
812	D	1	HM	3'-0"	7'-0"	1¾"	B	3/4"	2	1	HM	5-4	YES	1, 4, 6, 11, 12, 13, 19	EL. BA. ASSEMBLY (SEE DET. M/A-12) BRACE BOLT AT TOP LEAF
813	A	1	HM	3'-0"	7'-0"	1¾"	—	3/4"	1	1	HM	5-4	YES	3, 4, 7, 11, 12, 20, 13	
814	A	1	HM	3'-0"	7'-0"	1¾"	—	3/4"				5-1		1, 5, 7	DOOR TO FIT WITHIN EXIST. FRAME (CLR.)
815	A	1	HM	*	*	1¾"	B	3/4"				5-1		PROVIDE ALL NEW TO MATCH EXIST.	* MATCH EXIST. SIZE (V.I.F.)
816	A	1	HM	*	*	1¾"	B	3/4"				5-1		PROVIDE ALL NEW TO MATCH EXIST.	* MATCH EXIST. SIZE (V.I.F.)
902	EXISTING DOOR ASSEMBLY RELOCATED														

NOTE: ALL DOOR RETAINED HEAT SENSORS & LABEL SHALL BE UNDISTURBED UNLESS NOTED.

(A) FLUSH SINGLE DOOR — (D) DUTCH DOOR — (B) PAIR OF SLIDING DOORS — (C) DOUBLE EGRESS SMOKE DOORS

DOOR TYPES

FRAME TYPES

(1) JAMB (HEAD SIM) SCALE: 3"=1'-0" — (14) SAME AS TYPE 6 EXCEPT 1/2" FRAME — (2) JAMB (HEAD SIM) SCALE 3"=1'-0" — (12) JAMB (HEAD SIM) SCALE: 3"=1'-0" — (13) SAME AS TYPE 12 EXCEPT 1/2" FRAME

HARDWARE NOTES

20	CARD READER	CARD KEY SYSTEMS	FURNISHED & INSTALLED BY G.C. (SEE ABVE. NOTES)						19	ELECTRO MAGNETIC RELEASE	PULSON FIREMAN	WIRE TO ROOF ALARM PANEL AND TO DOOR AT LEVEL 1 FOR ALARM SYSTEM. CONTRACTOR TO COORDINATE WITH FIRE ALARM SYSTEM CONTRACTOR			18	ELECTRIC STRIKE	FOLGER-STEINS 310 1/2	5-8" OPERATION, PAINT TO MATCH DOOR FINISH (SEE ABVE. NOTES)
												DOORS TO BE DOPED FOR DOOR OPEN-CLOSED SIGNAL TO THE PATENT OF FIRE ALARM SYSTEM. DOORS TO BE UNLOCKED BY FIRE ALARM SYSTEM.			17	EXIT DEVICE	SARGENT 12-4900	W/ #612 OUTSIDE TRIM, #4900 SERIES MORTISE LOCK, #10 CURVED SINGLE PUSH BAR
															16	EXIT DEVICE	SARGENT 12-9400	W/ #612 OUTSIDE TRIM, #113 AUXILIARY OUTSIDE CYLINDER, #660 & #606 TOP & BOTTOM
															15	SURFACE BOLT	IVES #54	8" DUTCH DOOR BOLT W/ MORTISE STRIKE

PARTITION TYPES

(A) PARTITION SCALE: 3"=1'-0" — NOTE: FOR PARTITIONS RUNNING PERPENDICULAR TO CEILING, SEE DETAIL ON SHEET A-22

(B) PARTITION SCALE: 3"=1'-0"

(C) PARTITION SCALE: 3"=1'-0" 2 HR. FIRE RATING PER #1700.05

(G) PARTITION SCALE: 3"=1'-0" 2 HR. FIRE RATING PER #1700.05

(D) PARTITION SCALE: 3"=1'-0" 1 HR. FIRE RATING PER #1700.01

(E) PARTITION SCALE: 3"=1'-0"

(F) PARTITION SHAFT @ STAIR 5 & 9 2 HR. FIRE RATING PER #1700.05

(10) HEAD SCALE: 3"=1'-0" — (9) HEAD SCALE: 3"=1'-0" — (8) JAMB SCALE: 3"=1'-0" — (7) HEAD W/ TRANSOM SCALE: 3"=1'-0" — (6) HEAD W/ TRANSOM SCALE: 3"=1'-0" — (5) JAMB (HEAD SIM.) SCALE: 3"=1'-0" — (4) SLIDING DOOR JAMB SCALE: 3"=1'-0" — (3) SLIDING DOOR HEAD SCALE: 3"=1'-0"

SADDLE TYPES

(01) SCALE — (02) SCALE — (03) SCALE — (04) NO SCALE

NOTE: 3/4" UNDERCUT SHALL BE REQUIRED THRU FLOOR SLAB

(11) HEAD (JAMB SIM) SCALE: 3"=1'-0"

	REVISIONS
2/16/84	SUBMITTED TO PORT AUTHORITY FOR NOTICE
9/10/84	REVISED TO COMPLY WITH P.A. COMMENTS AND AREA OF REVISE
9/28/84	SUBMITTED TO PORT AUTHORITY FOR REVIEW AND GENERAL REVISION
11/16/84	SUBMITTED TO P.A. FOR REVIEW AND GENERAL REVISIONS TO COMPLY WITH COMMENTS

HARDWARE SCHEDULE

SET #	HARDWARE	MANUFACTURER	REMARKS
1	LOCKSET	"CORBIN" #2DB-DS3	FA BLDG STANDARD (MORTISE)
2	LOCKSET	"CORBIN" #2DB-LN	FA BLDG STANDARD (CYLINDRICAL)
3	LOCKSET	"CORBIN" #2DB-40	FA BLDG STANDARD
4	LOCKSET	"CORBIN" #2DB-DS3	FA BLDG STANDARD CODED FOR SEAK S-4 FOR DRS 2'-0" & 3'-0" MAN.
5	HINGES	FBB #74	1½ PAIR OF BUTTS FOR (HVY) FA BLDG STANDARD
6	STOP	"CORBIN" #3573½	FA BLDG STANDARD 1½" DIAM. STOP 1'-6" TALL FOR CARPET-UP SET
7	WEATHERSTRIP	"CORBIN" # 33	FA BLDG STANDARD CLOSURE (WEAR) THRESH. (2) FREE SWEEP DOOR (1½ THICK) & 1½ PAIR HINGES W/ TEFLON BOLT & 10" FL. #1218 STOP @ TOP & FLOOR GUIDE
8	SLIDING DOOR KIT	"CORBIN" # 2030	1½ DOOR & 1½ FRAME W/ TEFLON BOLT & 10" FL. #1218 STOP @ TOP & FLOOR GUIDE
9	FLUSH PULL	IVES #107 B/E	12" x 5" RECESSED FLUSH CAR LEAR
10	STOP	IVES #402½	WALL BUMPER
11	CONTACT ALARM	BED STANDARD	WIRED TO BOTH FIRE ENCLOSURE DOORS - WHEN DOOR CONTACT ALARM (MONITOR) SEE NOTE 6, 7 & 8 - UP TO 3 DOORS
12	HINGES	BED STANDARD	NON-REMOVABLE PINS IN BUTTS
13	DOOR BOLT	COLONIAL #429	MOUNT @ SEE ABVE
14	DOOR ALERT	DOREL #CL-2240	MODEL "NORMAL I"
15	SURFACE BOLT	IVES #54	8" DUTCH DOOR BOLT W/ MORTISE STRIKE

CEC
COMMODITIES EXCHANGE CENTER, INC.
FOUR WORLD TRADE CENTER
NEW YORK, NEW YORK 10048

EGRESS UPGRADE
PHASE 1&2

dwg title: DOOR & HARDWARE SCHEDULE, FRAME TYPES, PARTITION TYPES & SADDLE TYPES

CONSIGLIO DI NAPOLI & MAZZOTTA, P.C. ARCHITECTS
270 SEVENTH AVENUE NEW YORK, NEW YORK 10001 (212) 255-2600

project 1830 | scale NO SCALE | date 2/21/84 | dwg no. A-23