
REFURBISHMENT NOTES (B.O.H.)

1. PATCH DENTS & PAINT EXISTING WALL
2. PATCH HOLES, SPACKLE & PAINT EXISTING WALL
NOT USED 3. REFRAME & RECLAD GYP. WALL, SPACKLE & PAINT
NOT USED 4. REPLACE 4X8 FIBERGLASS PANEL & TRIM. (3 PANELS OR LESS PER SPACE)
NOT USED 4a. PROVIDE NEW FIBERGLASS PANEL COVERING OVER ENTIRE WALL SURFACE.
NOT USED 5. REGLUE & CLEAN EXISTING TORN OR PEELING WALL PAPER.
NOT USED 7. PROVIDE NEW BASE RAILS
NOT USED 8. PROVIDE NEW WALL GUARDS TO MATCH EXISTING
NOT USED 9. PROVIDE NEW CORNER GUARDS TO MATCH EXISTING
10. REPLACE BROKEN OR MISSING A.C.T. – VERIFY SIZE & TYPE IN FIELD. (10 TILES OR LESS PER SPACE) PAINT CEILING THROUGHOUT SPACE.
11. PROVIDE NEW A.C.T. CEILING, FRAMING SUPPORTS & GRID.
NOT USED 12. REPLACE DENT, BROKEN OR MISSING PERFORATED METAL CEILING TILES TO MATCH EXISTING. (TEN OR LESS PER SPACE)
NOT USED 12a. PROVIDE NEW PERFORATED METAL TILE CEILING THROUGHOUT SPACE.
13. REPLACE BROKEN OR MISSING V.C.T. WITH NEW TO MATCH EXISTING. (10 OR LESS PER SPACE)
NOT USED 14. PROVIDE NEW V.C.T. FLOOR THROUGHOUT SPACE.
NOT USED 15. REPLACE BROKEN OR MISSING CERAMIC TILE WITH NEW TO MATCH EXISTING. (TEN OR LESS PER SPACE)
16. PROVIDE NEW CERAMIC TILE THROUGHOUT SPACE.
17. PROVIDE NEW CARPET THROUGHOUT SPACE.
18. REPAINT EXISTING DOOR & FRAME TO MATCH EXISTING.
NOT USED 19. REPAIR OR REPLACE EXISTING DOOR & HARDWARE.
NOT USED 20. EXISTING DOORS HAVE BEEN REMOVED FROM FRAME & STORED ON SITE. DOORS ARE TO BE RE-HUNG & REFURBISHED AS REQUIRED. DOORS MAY REQUIRE NEW HINGES.
NOT USED 21. DOOR FRAME TO BE REPLACED WITH SIMILIAR FRAME. REHANG DOORS. (SEE NOTE 20)
NOT USED 21a. DOOR FRAME TO BE REPLACED WITH SIMILIAR FRAME. REHANG DOORS.
NOT USED 22. REPAIR OR REPLACE CLOSET DOOR, REHANG ON TRACK & SERVICE HARDWARE.
23. IN-FILL GWB PARTITION TO MATCH EXISTING WHERE DOOR & FRAME HAS BEEN DEMOLISHED. VERIFY PARTITION TYPE IN FIELD.
24. PATCH, REPAIR & RE-FINISH EXISTING WALL TO MATCH EXISTING WHERE ADJACENT WALL HAS BEEN REMOVED.
NOT USED 25. PROVIDE NEW VINYL WALL BASE TO MATCH EXISTING.
NOT USED 26. ADD SALVAGED CHAIR RAIL TO NEW PARTITION – ALIGN WITH EXISTING.
27. PROVIDE LIGHTWEIGHT CONCRETE OVER EXISTING RAMP TO MATCH ELEVATION OF REMAINDER OF ROOM.
NOT USED 28. PROVIDE RAMP OF LIGHTWEIGHT POURED CONCRETE TO BE SMOOTH, LEVEL, & TO HAVE A MAXIMUM SLOPE OF 1:12.
29. FLASH PATCH OVER EXISTING SLAB WITH LIGHTWEIGHT CONCRETE.
NOT USED 30. CLEAN & PAINT EXISTING CONCRETE SLAB.
NOT USED 31. REPAINT MULLIONS TO MATCH EXISTING, CLEAN GLASS ON BOTH SIDES.



LEGEND

- EXISTING TO REMAIN
- NEW NON-RATED
- EXISTING 1 HOUR RATED
- NEW 1 HOUR RATED
- EXISTING 2 HOUR RATED
- NEW 2 HOUR RATED

NF = (NEW FIXED MILLWORK)
RMWB = (MILLWORK BACK OF HOUSE)
RAWB = (REFURBISH MILLWORK)

NOTE: FLOATING BARS NL-77
QUANTITY = 2
FLOATING SIDE BARS NL-76
QUANTITY = 6

RECEIVED
OCT 11 1995
LESLIE E. ROBERTSON ASSOCIATES
211 E. 46th ST., N.Y., N.Y.C. 10017

WINDOWS ON THE WORLD
WORLD TRADE CENTER ONE
NEW YORK CITY, NEW YORK

HARDY HOLZMAN PFEIFFER ASSOCIATES

LANDLORD:
PORT AUTHORITY OF NY & NJ
WORLD TRADE DEPARTMENT
1 WORLD TRADE CENTER, 65TH FLOOR WEST
NEW YORK, NEW YORK 10048

OPERATOR:
B.E. WINDOWS CORPORATION
130 65th AVENUE
NEW YORK, NEW YORK 10010

ARCHITECT:
HARDY HOLZMAN PFEIFFER ASSOCIATES
902 BROADWAY, 13th FLOOR
NEW YORK, NEW YORK 10010

MEP ENGINEER:
ALTIERI SEBOR WIEBER
51 KNIGHT STREET
NORWALK, CONNECTICUT 06851

STRUCTURAL ENGINEER:
LESLIE E. ROBERTSON ASSOCIATES
16 E. 34th STREET, 15th FLOOR
NEW YORK, NEW YORK 10017

KITCHEN PLANNING:
CINI-LITTLE INTERNATIONAL INC.
501 MADISON AVENUE
NEW YORK, NEW YORK 10165

A/V ACOUSTICS:
SHAW-WILSON WILKIE
6 EAST 39th STREET
NEW YORK, NEW YORK 10016

LIGHTING:
CLINE BETTRIDGE BERNSTEIN LIGHTING
50 WEST 23rd STREET
NEW YORK, NEW YORK 10010

CODES/ ADA:
DAVID E. LEVINOWITZ, P.C.
70 WEST 40th STREET
NEW YORK, NEW YORK 10018

TOWER A · TOWER B · NORTH

NO.:	DATE:	REVISIONS:
		CONSTRUCTION DOCUMENTATION SUBMISSION
1	5/22/95	PA QUERIES/REVISIONS
2	6/5/95	PA QUERIES/REVISIONS
3	7/17/95	GENERAL REVISIONS
4	10/9/95	ISSUE FOR CONSTRUCTION

TITLE:
QUADRANT B
106TH FLOOR PLAN
SUITES C,D,E,F

HHPA PROJECT NO. 5466.03
DRAWING NO. A510
DATE: JULY 17, 1995
SCALE: 1/4"=1'-0"

TAA 951114.07