REFURBISHMENT NOTES (B.O.H.)

NOT USED	1	PATCH DENTS & PAINT EXISTING WALL
NOT USED	2	PATCH HOLES, SPACKLE & PAINT EXISTING WALL
NOT USED	3	REFRAME & RECLAD GYP. WALL, SPACKLE & PAINT
NOT USED	4	REPLACE 4X8 FIBERGLASS PANEL & TRIM. (3-PANELS OR LESS PER SPACE)
NOT USED	4a	PROVIDE NEW FIBERGLASS PANEL COVERING OVER ENTIRE WALL SURFACE
NOT USED	5	REGLUE & CLEAN EXISTING TORN OR PEELING WALL PAPER.
NOT USED	7	PROVIDE NEW BASE RAILS
NOT USED	8	PROVIDE NEW WALL GUARDS TO MATCH EXISTING
NOT USED	9	PROVIDE NEW CORNER GUARDS TO MATCH EXISTING
NOT USED	10	REPLACE BROKEN OR MISSING A.C.T. – VERIFY SIZE & TYPE IN FIELD. (10 TILES OR LESS PER SPACE) PAINT CEILING THROUGHOUT SPACE.
NOT USED	11	PROVIDE NEW A.C.T. CEILING, FRAMING SUPPORTS & GRID
NOT USED	12	REPLACE BENT, BROKEN OR MISSING PERFORATED METAL CEILING TILES TO MATCH EXISTING. (TEN OR LESS PER SPACE)
NOT USED	12a	PROVIDE NEW PERFORATED METAL TILE CEILING THROUGHOUT SPACE.
	13	REPLACE BROKEN OR MISSING V.C.T. WITH NEW TO MATCH EXISTING. (10 OR LESS PER SPACE)
NOT USED	14	PROVIDE NEW V.C.T. FLOOR THROUGHOUT SPACE.
NOT USED	15	REPLACE BROKEN OR MISSING CERAMIC TILE WITH NEW TO MATCH EXISTING. (TEN OR LESS PER SPACE)
NOT USED	16	PROVIDE NEW CERAMIC TILE THROUGHOUT SPACE.
NOT USED	17	PROVIDE NEW CARPET THROUGHOUT SPACE.
NOT USED	18	REPAINT EXISTING DOOR & FRAME TO MATCH EXISTING.
NOT USED	19	REPAIR OR REPLACE EXISTING DOOR & HARDWARE.
NOT USED	20	EXISTING DOORS HAVE BEEN REMOVED FROM FRAME & STORED ON SITE. DOORS ARE TO BE RE-HUNG & REFURBISHED AS REQUIRED. DOORS MAY REQUIRE NEW HINGES.
NOT USED	21	DOOR FRAME TO BE REPLACED WITH SIMILAR FRAME. REHANG DOORS. (SEE NOTE 20)
NOT USED	21a	DOOR FRAME TO BE REPLACED WITH SIMILAR FRAME. REHANG DOORS.
NOT USED	22	REPAIR OR REPLACE CLOSET DOOR, REHANG ON TRACK & SERVICE HARDWARE.
NOT USED	23	IN-FILL GWB PARTITION TO MATCH EXISTING WHERE DOOR & FRAME HAS BEEN DEMOLISHED. VERIFY PARTITION TYPE IN FIELD.
NOT USED	24	PATCH, REPAIR & RE-FINISH EXISTING WALL TO MATCH EXISTING WHERE ADJACENT WALL HAS BEEN REMOVED.
NOT USED	25	PROVIDE NEW VINYL WALL BASE TO MATCH EXISTING
NOT USED	26	ADD SALVAGED CHAIR RAIL TO NEW PARTITION – ALIGN WITH EXISTING.
NOT USED	27	PROVIDE LIGHTWEIGHT CONCRETE OVER EXISTING RAMP TO MATCH ELEVATION OF REMAINDER OF ROOM.
NOT USED	28	PROVIDE RAMP OF LIGHTWEIGHT POURED CONCRETE TO BE SMOOTH, LEVEL & TO HAVE A MAXIMUM SLOPE OF 1:12.
NOT USED	29	FLASH PATCH OVER EXISTING SLAB WITH LIGHTWEIGHT CONCRETE.
	30	CLEAN & PAINT EXISTING CONCRETE SLAB.
NOT USED	31	REPAINT MULLIONS TO MATCH EXISTING. CLEAN GLASS ON BOTH SIDES.

WINDOWS ON THE WORLD
WORLD TRADE CENTER ONE
NEW YORK CITY, NEW YORK

HARDY HOLZMAN PFEIFFER ASSOCIATES

LANDLORD:
PORT AUTHORITY OF NY & NJ
WORLD TRADE DEPARTMENT, 66TH FLOOR WEST
1 WORLD TRADE CENTER, NEW YORK, NEW YORK 10048

OPERATOR:
B.E. WINDOWS CORPORATION
350 FIFTH AVENUE
NEW YORK, NEW YORK 10010

ARCHITECT:
HARDY HOLZMAN PFEIFFER ASSOCIATES
115 FIFTH AVENUE, 12TH FLOOR
NEW YORK, NEW YORK 10010

MEP ENGINEER:
ALTIERI SEBOR WIEBER
333 WESTPORT AVENUE
NORWALK, CONNECTICUT 06851

STRUCTURAL ENGINEER:
LESLIE E. ROBERTSON ASSOCIATES
250 EAST 49TH STREET
NEW YORK, NEW YORK 10017

KITCHEN PLANNING:
CINI-LITTLE INTERNATIONAL, INC.
420 MADISON AVENUE
NEW YORK, NEW YORK 10165

A/V ACOUSTICS:
CHRIS MISSEN WILKE
5 EAST 16TH STREET
NEW YORK, NEW YORK 10016

LIGHTING:
CLINE BETTRIDGE BERNSTEIN LIGHTING
150 WEST 22ND STREET
NEW YORK, NEW YORK 10010

CODE/ ADA:
DAVID E. LIEBOWITZ, P.C.
270 MADISON AVENUE
NEW YORK, NEW YORK 10018

NO.:	DATE:	REVISIONS:
CONSTRUCTION DOCUMENTATION SUBMISSION		
1	10/9/95	ISSUE FOR CONSTRUCTION

TITLE: QUADRANT C
106TH FLOOR
FLOORING PLAN

HHPA PROJECT NO. 5466.03
DRAWING NO. 1115
DATE: JULY 17, 1995
SCALE: 1/16"=1'-0"

TAA 951114.07