A/V CLOSET 311A — REFURBISHMENT NOTES

1. PATCH DENTS & PAINT EXISTING WALL
2. PATCH HOLES, SPACKLE & PAINT EXISTING WALL
3. NOT USED — REFRAME & RECLAD GYP. WALL, SPACKLE & PAINT
4. REPLACE 4X8 FIBERGLASS PANEL & TRIM. (3 PANELS OR LESS PER SPACE)
5. NOT USED — PROVIDED NEW FIBERGLASS PANEL COVERING OVER ENTIRE WALL SURFACE.
6. REGLUE & CLEAN EXISTING TORN OR PEELING WALL PAPER.
7. PROVIDE NEW BASE RAILS
8. PROVIDE NEW WALL GUARDS TO MATCH EXISTING
9. PROVIDE NEW CORNER GUARDS TO MATCH EXISTING
10. NOT USED — REPLACE BROKEN OR MISSING A.C.T. – VERIFY SIZE & TYPE IN FIELD. (10 TILES OR LESS PER SPACE)
11. NOT USED — PAINT CEILING THROUGHOUT SPACE
12. NOT USED — PROVIDE NEW A.C.T. CEILING, FRAMING SUPPORTS & GRID
13. NOT USED — REPLACE DENT, BROKEN OR MISSING PERFORATED METAL CEILING TILES TO MATCH EXISTING. (TEN OR LESS PER SPACE)
14. NOT USED — PROVIDE NEW PERFORATED METAL TILE CEILING THROUGHOUT SPACE
15. NOT USED — REPLACE BROKEN OR MISSING V.C.T. WITH NEW TO MATCH EXISTING. (10 OR LESS PER SPACE)
16. NOT USED — PROVIDE NEW V.C.T. FLOOR THROUGHOUT SPACE.
17. NOT USED — REPLACE BROKEN OR MISSING CERAMIC TILE WITH NEW TO MATCH EXISTING. (TEN OR LESS PER SPACE)
18. NOT USED — PROVIDE NEW CERAMIC TILE THROUGHOUT SPACE.
19. NOT USED — PROVIDE NEW CARPET THROUGHOUT SPACE.
20. NOT USED — REPAINT EXISTING DOOR & FRAME TO MATCH EXISTING.
21. NOT USED — REPAIR OR REPLACE EXISTING DOOR & HARDWARE.
22. NOT USED — EXISTING DOORS HAVE BEEN REMOVED FROM FRAME & STORED ON SITE. DOORS ARE TO BE RE-HUNG & REFURBISHED AS REQUIRED. DOORS MAY REQUIRE NEW HINGES.
23. NOT USED — DOOR FRAME TO BE REPLACED WITH SIMILIAR FRAME. REHANG DOORS. (SEE NOTE 20)
24. NOT USED — DOOR FRAME TO BE REPLACED WITH SIMILIAR FRAME. REHANG DOORS.
25. NOT USED — REPAIR OR REPLACE CLOSET DOOR, REHANG ON TRACK & SERVICE HARDWARE.
26. NOT USED — IN-FILL EXIST PARTITION TO MATCH EXISTING WHERE DOOR & FRAME HAS BEEN DEMOLISHED. VERIFY PARTITION TYPE IN FIELD.
27. NOT USED — PATCH, REPAIR & RE-FINISH EXISTING WALL TO MATCH EXISTING WHERE ADJACENT WALL HAS BEEN REMOVED.
28. NOT USED — PROVIDE NEW VINYL WALL BASE TO MATCH EXISTING.
29. NOT USED — ADD SALVAGED CHAIR RAIL TO NEW PARTITION – ALIGN WITH EXISTING.
30. NOT USED — PROVIDE LIGHTWEIGHT CONCRETE OVER EXISTING RAMP TO MATCH ELEVATION OF REMAINDER OF ROOM.
31. NOT USED — PROVIDE RAMP OF LIGHTWEIGHT POURED CONCRETE TO BE SMOOTH, LEVEL & TO HAVE A MAXIMUM SLOPE OF 1:12.
32. NOT USED — PATCH OVER EXISTING SLAB WITH LIGHTWEIGHT CONCRETE.
33. NOT USED — CLEAN & PAINT EXISTING CONCRETE SLAB.
34. NOT USED — REPAINT MULLIONS TO MATCH EXISTING, CLEAN GLASS ON BOTH SIDES.

HUDSON "C" 311 · HUDSON "B" 310 EL. +0'-0" · HUDSON "A" 309 · PRE-FUNCTION 312 · STORAGE 311B · VESTIBULE 407 · WOMENS 408A · MENS 408B · MECH 511 · PRE-FAB WALK-IN REF. "A" 512A · F.E. #99 · F.E. #50 · A/C SHAFT · TOILET 519 · FIRE PROTECTION CLOSET 518 · ELEC. CL. 517 · TOILET 520 · P.E. #95 · P.E. #94 · P.E. #93 · STAIR #3 516 · STORAGE 514A · FBC CORRIDOR 514 · SERVICE 513 EL. +2'-0" FBC · STORAGE 406A · JAN. CLOSET 406B · MENS TOILET 406C · STORAGE EL. +11'-1/2" 512 · ELEC. CL. 508 · SHAFT · P.E. #9 · P.E. #8 · 5'6-1/2" · STORAGE · EXISTING REF. 515 · SHAFT · TEL. CL. · STORAGE 309B · STORAGE 510 · MENS RESTROOM 403 EL. +11'-1-1/2" · URINALS 404 · ELEC. CLOSET 509 · A/C SHAFT · HANDRAIL/VERTICLE POSTS KICKPLATE/CONNECTOR COVER · STORAGE 309A · TOILET 306A · TOILET 306B · QUIET 306 · QUIET 308A · CORRIDOR 402A · GIFTS 206 · SLOPE TO DRAIN · VESTIBULE 205 · HUDSON LOUNGE 308 · ENTRY 307 EL. +0'-0" · EL. +2'-8" · ARRIVAL GALLERY 200 · H.C. LIFT #3 · CORRIDOR 402 · RAMP 1:12 ON · TELEPHONE 405 · COATS 400 EL. +0'-0" · COAT CHECK 401 EL. +4'-0-1/2" · STAIRS 501 · WINE STORAGE 204A · STAIRS 502 · WINE STORAGE 204B · AV CLOSET 303A · PRE-FUNCTION 304 · LIBERTY SUITE 110 SEATING CAPACITY 303 · LIBERTY PRE-FUNCTION 50 SEATING CAPACITY 301 · 302 · 300 · CELLAR IN THE SKY 204 EL. +5'6-3/4" · EL. +5'5-1/2" · STORAGE BELOW 300A · EL. +5'5" 1/2" DOOR FINISH TO MATCH ADJACENT 203 · SEE MILLWORK SCHEDULE TYP. · PAINTED OUT WINDOWS MULLIONS AND WALLS · TYPICAL ALL PERIMETER FRONT OF HOUSE MULLIONS

FOR MEZZANINE DISHWASHING FINISHES SEE DRAWING I-127

359 357 355 353 351 349 347 345 343 341 339 337 335 333 331 329 327 325

1001 1002 1003 1004 1005

RECEIVED
OCT 11 1995
LESLIE E. ROBERTSON ASSOCIATES
211 E. 46th ST., N.Y., N.Y.C. 10017

WINDOWS ON THE WORLD
WORLD TRADE CENTER ONE
NEW YORK CITY, NEW YORK
HARDY HOLZMAN PFEIFFER ASSOCIATES

LANDLORD:
PORT AUTHORITY OF NY & NJ
1 WORLD TRADE CENTER, 107TH FLOOR WEST
NEW YORK, NEW YORK 10048

OPERATOR:
B.E. WINDOWS CORPORATION
1185 6TH AVENUE
NEW YORK, NEW YORK 10010

ARCHITECT:
HARDY HOLZMAN PFEIFFER ASSOCIATES
909 BROADWAY, 17TH FLOOR
NEW YORK, NEW YORK 10010

MEP ENGINEER:
ALTIERI SEBOR WIEBER
50 LOCUST AVENUE
NORWALK, CONNECTICUT 06851

STRUCTURAL ENGINEER:
LESLIE E. ROBERTSON ASSOCIATES
211 EAST 46TH STREET
NEW YORK, NEW YORK 10017

KITCHEN PLANNING:
CINI-LITTLE INTERNATIONAL, INC.
521 FIFTH AVENUE
NEW YORK, NEW YORK 10165

A/V ACOUSTICS:
ZWEIN MILSOM WILKE
250 EAST 39TH STREET
NEW YORK, NEW YORK 10016

LIGHTING:
CLINE BETTRIDGE BERNSTEIN LIGHTING
30 WEST 22ND STREET
NEW YORK, NEW YORK 10010

CODE/ ADA:
DAVID E. LIEBOWITZ, P.C.
70 WEST 36TH STREET
NEW YORK, NEW YORK 10018

TOWER A · TOWER B · NORTH

NO.:	DATE:	REVISIONS:
CONSTRUCTION DOCUMENTATION SUBMISSION		
1	10/9/95	ISSUE FOR CONSTRUCTION

TITLE: QUADRANT C
107TH FLOOR
FINISH PLAN

HHPA PROJECT NO. 5466.03
DRAWING NO. 1119
DATE: JULY 31, 1995
SCALE: 1/4"=1'-0"

TAA 951114.07