REFURBISHMENT NOTES (B.O.H.)

	1	PATCH DENTS & PAINT EXISTING WALL.
NOT USED	2	PATCH HOLES, SPACKLE & PAINT EXISTING WALL
NOT USED	3	REFRAME & RECLAD GYP. WALL SPACKLE & PAINT
	4	REPLACE 4X8 FIBERGLASS PANEL & TRIM. (3 PANELS OR LESS PER SPACE)
NOT USED	4a	PROVIDE NEW FIBERGLASS PANEL "COVERING OVER ENTIRE WALL SURFACE
NOT USED	5	REGLUE & CLEAN EXISTING TORN OR PEELING WALL PAPER.
NOT USED	7	PROVIDE NEW BASE RAILS
NOT USED	8	PROVIDE NEW WALL GUARDS TO MATCH EXISTING
NOT USED	9	PROVIDE NEW CORNER GUARDS TO MATCH EXISTING
NOT USED	10	REPLACE BROKEN OR MISSING A.C.T. – VERIFY SIZE & TYPE IN FIELD. (10 TILES OR LESS PER SPACE) PAINT CEILING THROUGHOUT SPACE.
NOT USED	11	PROVIDE NEW A.C.T. CEILING, FRAMING SUPPORTS & GRID
NOT USED	12	REPLACE BENT, BROKEN OR MISSING PERFORATED METAL CEILING TILES TO MATCH EXISTING. (TEN OR LESS PER SPACE)
NOT USED	12a	PROVIDE NEW PERFORATED METAL TILE CEILING THROUGHOUT SPACE.
NOT USED	13	REPLACE BROKEN OR MISSING V.C.T. WITH NEW TO MATCH EXISTING. (10 OR LESS PER SPACE)
NOT USED	14	PROVIDE NEW V.C.T. FLOOR THROUGHOUT SPACE.
NOT USED	15	REPLACE BROKEN OR MISSING CERAMIC TILE WITH NEW TO MATCH EXISTING. (TEN OR LESS PER SPACE)
NOT USED	16	PROVIDE NEW CERAMIC TILE THROUGHOUT SPACE.
NOT USED	17	PROVIDE NEW CARPET THROUGHOUT SPACE.
	18	REPAINT EXISTING DOOR & FRAME TO MATCH EXISTING.
	19	REPAIR OR REPLACE EXISTING DOOR & HARDWARE.
NOT USED	20	EXISTING DOORS HAVE BEEN REMOVED FROM FRAME & STORED ON SITE. DOORS ARE TO BE RE-HUNG & REFURBISHED AS REQUIRED. DOORS MAY REQUIRE NEW HINGES.
NOT USED	21	DOOR FRAME TO BE REPLACED WITH SIMILAR FRAME. REHANG DOORS. (SEE NOTE 20)
NOT USED	21a	DOOR FRAME TO BE REPLACED WITH SIMILAR FRAME. REHANG DOORS.
NOT USED	22	REPAIR OR REPLACE CLOSET DOOR, REHANG ON TRACK & SERVICE HARDWARE.
	23	IN-FILL GWB PARTITION TO MATCH EXISTING WHERE DOOR & FRAME HAS BEEN DEMOLISHED. VERIFY PARTITION TYPE IN FIELD.
	24	PATCH, REPAIR & RE-FINISH EXISTING WALL TO MATCH EXISTING WHERE ADJACENT WALL HAS BEEN REMOVED.
NOT USED	26	PROVIDE NEW VINYL WALL BASE TO MATCH EXISTING.
NOT USED	26	ADD SALVAGED CHAIR RAIL TO NEW PARTITION – ALIGN WITH EXISTING.
NOT USED	27	PROVIDE LIGHTWEIGHT CONCRETE OVER EXISTING RAMP TO MATCH ELEVATION OF REMAINDER OF ROOM.
NOT USED	28	PROVIDE RAMP OF LIGHTWEIGHT POURED CONCRETE TO BE SMOOTH, LEVEL & TO HAVE A MAXIMUM SLOPE OF 1:12.
NOT USED	29	FLASH PATCH OVER EXISTING SLAB WITH LIGHTWEIGHT CONCRETE.
NOT USED	30	CLEAN & PAINT EXISTING CONCRETE SLAB.
NOT USED	31	REPAINT MULLIONS TO MATCH EXISTING. CLEAN GLASS ON BOTH SIDES.

NOTES:

P-31 SN — TYPICAL ALL BACK OF HOUSE WD BASES

P-31 SG — TYPICAL ALL BACK OF HOUSE DOORS

RECEIVED
OCT 11 1995
LESLIE E. ROBERTSON ASSOCIATES
211 E. 46th ST., N.Y., N.Y.C. 10017

WINDOWS ON THE WORLD
WORLD TRADE CENTER ONE
NEW YORK CITY, NEW YORK

HARDY HOLZMAN PFEIFFER ASSOCIATES

LANDLORD:
PORT AUTHORITY OF NY & NJ
WORLD TRADE DEPARTMENT
1 WORLD TRADE CENTER, 65th FLOOR WEST
NEW YORK, NEW YORK 10048

OPERATOR:
B.E. WINDOWS CORPORATION
1 THE STREAM SIDE
NEW YORK, NEW YORK 10010

ARCHITECT:
HARDY HOLZMAN PFEIFFER ASSOCIATES
400 MADISON AVENUE
NEW YORK, NEW YORK 10017

MEP ENGINEER:
ALTIERI SEBOR WIEBER
100 PROGRESS PARKWAY
NORWALK, CONNECTICUT 06851

STRUCTURAL ENGINEER:
LESLIE E. ROBERTSON ASSOCIATES
211 E. 46th STREET
NEW YORK, NEW YORK 10017

KITCHEN PLANNING:
CINI-LITTLE INTERNATIONAL, INC.
1290 AVENUE OF THE AMERICAS
NEW YORK, NEW YORK 10165

A/V ACOUSTICS:
ZIMER MILSON WILKE
41 EAST 57th STREET
NEW YORK, NEW YORK 10016

LIGHTING:
CLINE BERTRIDGE BERNSTEIN LIGHTING
150 E. 58th STREET
NEW YORK, NEW YORK 10010

CODE/ ADA:
DAVID E. LIEBOWITZ, P.C.
11 WEST 30th STREET
NEW YORK, NEW YORK 10018

TOWER A — TOWER B — NORTH

NO.:	DATE:	REVISIONS:
CONSTRUCTION DOCUMENTATION SUBMISSION		
1	10/6/95	ISSUE FOR CONSTRUCTION

TITLE: QUADRANT C
106TH FLOOR
FINISH PLAN

HHPA PROJECT NO. 5466.03 — DRAWING NO. 1123

DATE: JULY 17, 1995

SCALE: 1/4"=1'-0"

TAA 951114.07