SKILLING - HELLE - CHRISTIANSEN - ROBERTSON Structural & Civil Engineers

PROJECT THE WORLD TRADE CENTER | TITLE TEMP. FRAMING FOR ELEVATOR #6 & #7 | DATE 12-15-67

REVISIONS
1-12-68
3-29-68
1-3-69
2-3-69
3-3-69
4-1-69
Printed 5-1-69

GENERAL NOTES

1. Provide 3 beams each MK [B1], [B2] & [B3]. Provide 2 beams each MK [B4] & [B5].
2. Connection material shall be shop welded to column shafts, except where column has been fabricated complete and stored, Connection material shall be fabricated and supplied under contract WTC 217.00 and field welded to column under contract WTC 230.00.
3. All temporary connection material for elevator framing shall be removed after elevator machinery has been relocated

INDEX

6-AB9-0	Date sheet
6-AB9-1	General Notes & Index
6-AB9-2	Temporary Framing Plan for Elevator #7 at Floors 16, 33, 48, 63
6-AB9-3	Temporary Framing Plan for Elevator #6 at Floors 12, 24, 41, 54
6-AB9-4	Temporary Framing for Elevator #6 & #7 - Detail A & B
6-AB9-5	Temporary Framing for Elevator #6 & #7 - Detail D
6-AB9-6	Temporary Framing for Elevator #6 & #7 - Detail C
6-AB9-7	Temporary Framing for Elevator #6 & #7 - Detail E
6-AB9-8	Temporary Framing for Elevator PE #44 at Floor 7
6-AB9-9	Temporary Framing for Elevator PE #44, details A & B.

LICENSED PROFESSIONAL ENGINEER
LESLIE E. ROBERTSON
No. 34360
UNIVERSITY OF THE STATE OF NEW YORK