SKILLING - HELLE - CHRISTIANSEN - ROBERTSON — Structural & Civil Engineers

PROJECT: THE WORLD TRADE CENTER | TITLE: FLOOR TRUSSES - INDEX & GENERAL NOTES | DATE: 10/20/67

REVISIONS
1-3-68
1-26-68
2-15-68
4-1-68

7-AB2- 1	Floor Trusses - Index & General Notes	
7-AB2- 2	Floor Truss	24T7, 24T7A, 24T7B
7-AB2- 3	Floor Truss	24T8, 24T8A, 24T8B
7-AB2- 4	Floor Truss	24T9, 24T9A
7-AB2- 5	Floor Truss	24T10, 24T10A, 24T10B
7-AB2- 6	Bridging	24T11, 24T11A,
7-AB2- 7	Bridging	24T12,
7-AB2- 8	Bridging	24T13, 13A, 13B, 13C,
7-AB2- 8.1	Void	
7-AB2- 9	Floor Truss	24T14, 24T14A, 24T14B
7-AB2- 10	Floor Truss	24T15, 24T15A, 24T15B
7-AB2- 11	Floor Truss	24T16, 24T16A, 24T16B
7-AB2- 12	Floor Truss	24T7C, 24T7D, 24T7E
7-AB2- 13	Floor Truss	24T10C, 24T10D, 24T10E
7-AB2- 14	Bridging	24T11B, 11C, 11D
7-AB2- 15	Bridging	24T13D, 13E
7-AB2- 16	Floor Truss	24T7F, 24T7G, 24T7H
7-AB2- 17	Floor Truss	24T8C, 24T8D, 24T8E
7-AB2- 18	Floor Truss	24T10F, 24T10G, 24T10H
7-AB2- 19	Floor Truss	24T14C, 24T14D
7-AB2- 20	Floor Truss	24T15C, 15D
7-AB2- 21	Floor Truss	24T7I, 24T7J, 24T7K
7-AB2- 22	Floor Truss	24T8F, 24T8G, 24T8H
7-AB2- 23	Floor Truss	24T9B, 24T9C
7-AB2- 24	Floor Truss	24T10I, 24T10J, 24T10K
7-AB2- 25	Floor Truss	24T16C

GENERAL NOTES

1. All material, including detail material not shown on these dwgs., to be Fy = 50 unless otherwise noted.

2. All floor truss angles have short legs vertical,

3. Horizontal shear forces between truss panel points and the composite concrete slab are indicated [ ] in the truss elevations. Where no shear force is given, the connection shall be proportioned for a force of 5 Kips ([5]). See Dwg. 7-AB1-1 for additional notes for additional shear forces.

4. See Dwg. 7-AB1-1 for notes regarding the joint occurrence of longitudinal and transverse horizontal shear force.

5. Chord stresses are indicated in truss elevations as "P = ". Where no force is given each truss chord splice connection shall be proportioned for a minimum force of 23 Kips (P = 23).

6. Vertical shear forces between adjacent panels are indicated in truss elevations are "V = ". Where no force is given, shear transfer connection shall be proportioned for a minimum force of 5 Kips (V = 5). Connections shall be proportioned for a shear force of both positive sign and negative sign.

7. Contractor shall supply representative calculations and/or test results for each connection proportioned by the Contractor. All connections, details and the like are subject to approval by the Engineer.

8. End reactions of each truss are indicated in truss elevations as "R = ". Where no force is given, end connections shall be proportioned for a minimum reaction of 9 Kips (R = 9).

9. Truss shear, indicating minimum requirements for each truss web member, is tabulated across the bottom of the truss elevations. Where no shear is given, web members and their connections shall be proportioned for a minimum shear of (2.2) Kips.

REGISTERED PROFESSIONAL ENGINEER — LESLIE E. ROBERTSON — No. 24360 — STATE OF NEW YORK