SKILLING - HELLE - CHRISTIANSEN - ROBERTSON Structural & Civil Engineers

PROJECT THE WORLD TRADE CENTER | TITLE FLOOR PANELS-INDEX & GENERAL NOTES | DATE 10/20/67

REVISIONS

1-3-68
2-15-68
4-1-68
1-3-69
1-6-69
2-3-69
3-3-69
4-1-69

7-AB3- 1	Floor Panel - Index & General Notes
7-AB3- 2	Floor Panel Dimension Schedule 1
7-AB3- 3	Floor Panel A1
7-AB3- 4	Floor Panel A1 G/E & A1 J/G
7-AB3- 5	Floor Panel B1
7-AB3- 6	Floor Panel BR1
7-AB3- 7	Floor Panel C1
7-AB3- 8	Floor Panel CR1
7-AB3- 9	Floor Panel D1
7-AB3-10	Floor Panel DR1
7-AB3-11	Floor Panel E1
7-AB3-12	Floor Panel ER1
7-AB3-13	Floor Panel F1
7-AB3-14	Floor Panel FR1
7-AB3-15	Floor Panel G1
7-AB3-16	Floor Panel GR1
7-AB3-17	Floor Panel H1
7-AB3-18	Floor Panel HR1 & HR6
7-AB3-19	Floor Panel J1
7-AB3-20	Floor Panel K1
7-AB3-21	Floor Panel KR1
7-AB3-22	Floor Panel M1
7-AB3-23	Floor Panel MR1
7-AB3-24	Floor Panel Dimension Schedule 2
7-AB3-25	Floor Panel A2
7-AB3-26	Floor Panel B2
7-AB3-27	Floor Panel BR2
7-AB3-28	Floor Panel C2
7-AB3-29	Floor Panel CR2
7-AB3-30	Floor Panel D2
7-AB3-31	Floor Panel DR2
7-AB3-32	Floor Panel E2
7-AB3-33	Floor Panel ER2
7-AB3-34	Floor Panel F2
7-AB3-35	Floor Panel FR2
7-AB3-36	Floor Panel G2
7-AB3-37	Floor Panel GR2
7-AB3-38	Floor Panel H2
7-AB3-39	Floor Panel HR2 & 7
7-AB3-40	Floor Panel J2
7-AB3-41	Floor Panel Dimension Schedule 3
7-AB3-42	Floor Panel A3
7-AB3-43	Floor Panel B3
7-AB3-44	Floor Panel BR3
7-AB3-45	Floor Panel C3
7-AB3-46	Floor Panel CR3
7-AB3-47	Floor Panel D3
7-AB3-48	Floor Panel DR3
7-AB3-49	Floor Panel E3
7-AB3-55	Floor Panel 8R8
7-AB3-56	Floor Panel C8
7-AB3-57	Floor Panel CR8
7-AB3-58	Floor Panel D8
7-AB3-59	Floor Panel DR8
7-AB3-60	Floor Panel E8
7-AB3-61	Floor Panel ER8
7-AB3-62	Floor Panel F8
7-AB3-63	Floor Panel FR8
7-AB3-70	Floor Panel Dimension Schedule 5
7-AB3-71	Floor Panel D5
7-AB3-72	Floor Panel DR5
7-AB3-73	Floor Panel E5
7-AB3-74	Floor Panel ER5
7-AB3-75	Floor Panel F5
7-AB3-76	Floor Panel FR5
7-AB3-77	Floor Panel C6
7-AB3-78	Floor Panel CR6
7-AB3-79	Floor Panel C7
7-AB3-80	Floor Panel CR7

LICENSED PROFESSIONAL ENGINEER
LESLIE E. ROBERTSON
No. 34360
UNIVERSITY OF THE STATE OF NEW YORK

GENERAL NOTES:

1. Material for steel deck supporting members ∠ 3 x 2 to be Fy = 50 unless otherwise noted.

2. Deck beam angles and miscellaneous angles called for on floor panel drawings have long legs vertical.

3. Except as otherwise indicated, all ∠ 3 x 2 deck supports shall be continuous.

4. Numbers shown on floor panel drawings thus ( ) are vertical interaction forces in Kips between each C32 truss and the 24T truss.

   Where no interaction force is given, the connection shall be proportioned for a minimum connection of 5 Kips. All connections shall be proportioned for a tensile as well as a compressive interaction force of the specified value.

5. Contractor shall supply representative calculations and/or test results for each connection proportioned by the Contractor. All connections, details and the like are subject to approval by the Engineer.

6. Connection of ∠ 3 x 2 deck support beams to C32 trusses shall