SKILLING - HELLE - CHRISTIANSEN - ROBERTSON Structural & Civil Engineers

PROJECT THE WORLD TRADE CENTER | TITLE FLOOR PANELS - INDEX & GENERAL NOTES | DATE 10/20/67

REVISIONS

1-3-68
2-15-68
4-1-68

7-AB3- 1 Floor Panel Index & General Notes
7-AB3- 2 Floor Panel Dimension Schedule 1
7-AB3- 3 Floor Panel A1
7-AB3- 4 Floor Panel A1 G/E & A1 J/G
7-AB3- 5 Floor Panel B1
7-AB3- 6 Floor Panel BR1
7-AB3- 7 Floor Panel C1
7-AB3- 8 Floor Panel CR1
7-AB3- 9 Floor Panel D1
7-AB3- 10 Floor Panel DR1
7-AB3- 11 Floor Panel E1
7-AB3- 12 Floor Panel ER1
7-AB3- 13 Floor Panel F1
7-AB3- 14 Floor Panel FR1
7-AB3- 15 Floor Panel G1
7-AB3- 16 Floor Panel GR1
7-AB3- 17 Floor Panel H1
7-AB3- 18 Floor Panel HR1 & HR6
7-AB3- 19 Floor Panel J1
7-AB3- 20 Floor Panel K1
7-AB3- 21 Floor Panel KR1
7-AB3- 22 Floor Panel M1
7-AB3- 23 Floor Panel MR1
7-AB3- 24 Floor Panel Dimension Schedule 2
7-AB3- 25 Floor Panel A2
7-AB3- 26 Floor Panel B2
7-AB3- 27 Floor Panel BR2
7-AB3- 28 Floor Panel C2
7-AB3- 29 Floor Panel CR2
7-AB3- 30 Floor Panel D2
7-AB3- 31 Floor Panel DR2
7-AB3- 32 Floor Panel E2
7-AB3- 33 Floor Panel ER2
7-AB3- 34 Floor Panel F2
7-AB3- 35 Floor Panel FR2
7-AB3- 36 Floor Panel G2
7-AB3- 37 Floor Panel GR2
7-AB3- 38 Floor Panel H2
7-AB3- 39 Floor Panel HR2 & 7
7-AB3- 40 Floor Panel J2
7-AB3- 41 Floor Panel Dimension Schedule 3
7-AB3- 42 Floor Panel A3
7-AB3- 43 Floor Panel B3
7-AB3- 44 Floor Panel BR3
7-AB3- 45 Floor Panel C3
7-AB3- 46 Floor Panel CR3
7-AB3- 47 Floor Panel D3
7-AB3- 48 Floor Panel DR3
7-AB3- 49 Floor Panel E3
7-AB3- 50 Floor Panel ER3
7-AB3- 51 Floor Panel F3
7-AB3- 53 Floor Panel Dimension Schedule 4
7-AB3- 54 Floor Panel A4
7-AB3- 55 Floor Panel B4
7-AB3- 56 Floor Panel BR4
7-AB3- 57 Floor Panel C4
7-AB3- 58 Floor Panel CR4
7-AB3- 59 Floor Panel D4
7-AB3- 60 Floor Panel DR4
7-AB3- 61 Floor Panel E4
7-AB3- 62 Floor Panel ER4
7-AB3- 63 Floor Panel F4
7-AB3- 64 Floor Panel FR4
7-AB3- 65 Floor Panel G4
7-AB3- 66 Floor Panel GR4
7-AB3- 67 Floor Panel H4
7-AB3- 68 Floor Panel HR4 & 8
7-AB3- 69 Floor Panel J4
7-AB3- 70 Floor Panel Dimension Schedule 5
7-AB3- 71 Floor Panel D5
7-AB3- 72 Floor Panel DR5
7-AB3- 73 Floor Panel E5
7-AB3- 74 Floor Panel ER5
7-AB3- 75 Floor Panel F5
7-AB3- 76 Floor Panel FR5
7-AB3- 77 Floor Panel C6
7-AB3- 78 Floor Panel CR6
7-AB3- 79 Floor Panel C7
7-AB3- 80 Floor Panel CR7

GENERAL NOTES:

1. Material for steel deck supporting members ∠3x2 to be Fy = 50 unless otherwise noted.
2. Deck beam angles and misc. angles called for on floor panel dwgs. have long legs vertical.
3. Except as otherwise indicated, all ∠3x2 deck supports shall be continuous.
4. Numbers shown on floor panel drawings thus ( ) are vertical interaction forces in Kips between each C32 truss and the 24T truss.
   Where no interaction force is given, the connection shall be proportioned for a minimum connection of 5 Kips. All connections shall be proportioned for a tensile as well as a compressive interaction force of the specified value.
5. Contractor shall supply representative calculations and/or test results for each connection proportioned by the

LESLIE E. ROBERTSON ... No. 24300 ... STATE OF NEW YORK