SKILLING - HELLE - CHRISTIANSEN - ROBERTSON — Structural & Civil Engineers

PROJECT: THE WORLD TRADE CENTER | TITLE: FLOOR PANEL DETAILS - INDEX & GENERAL NOTES | DATE: 1-3-68

REVISIONS

4-1-68

| | | | |
|---|---|---|---|
| 7-AB4- 1 | Floor Panel Details, Index & General Notes | 7-AB4- 42 | Floor Panel - Detail E61-E67 |
| 7-AB4- 2 | Schedule of Details - Tower A | 7-AB4- 43 | Floor Panel - Detail E60 & E68 |
| 7-AB4- 2.1 | Schedule of Details - Tower A | 7-AB4- 44 | Floor Panel - Detail E61-E67 |
| 7-AB4- 2.2 | Schedule of Details - Tower B | 7-AB4- 45 | Floor Panel - Detail E65 |
| 7-AB4- 2.3 | Schedule of Details - Tower B | 7-AB4- 46 | Floor Panel - Detail E60 & E68 |
| 7-AB4- 2.4 | Schedule of Details - Tower B | 7-AB4- 47 | Floor Panel - Detail E60-E68 |
| 7-AB4- 3 | Floor Panel - Detail E1-E3 | 7-AB4- 48 | Floor Panel - Detail E61-E64 |
| 7-AB4- 3.1 | Floor Panel - Detail E1-E4 | 7-AB4- 49 | Floor Panel - Detail E60 & E66-E67 |
| 7-AB4- 4 | Floor Panel - Detail E5 & E5A | | |
| 7-AB4- 5 | Floor Panel - Detail E6 | | |
| 7-AB4- 6 | Floor Panel - Detail E6 | | |
| 7-AB4- 7 | Floor Panel - Detail E8 | | |
| 7-AB4- 8 | Floor Panel - Detail E9 & | | |
| 7-AB4- 9 | Floor Panel - Detail E10 | | |
| 7-AB4- 10 | Floor Panel - Detail E11 | | |
| 7-AB4- 11 | Floor Panel - Detail E12,E13,E14,E15 | | |
| 7-AB4- 11.1 | Floor Panel - Detail E12,E13,E14,E15 | | |
| 7-AB4- 12 | Floor Panel - Detail E16 | | |
| 7-AB4- 13 | Floor Panel - Detail E17 & E18 | | |
| 7-AB4- 14 | Floor Panel - Detail E19,E21,E22 | | |
| 7-AB4- 14.1 | Floor Panel - Detail E20 | | |
| 7-AB4- 15 | Floor Panel - Detail E23,E24 | | |
| 7-AB4- 15.1 | Floor Panel - Detail E25,E26 | | |
| 7-AB4- 16 | Floor Panel - Detail E27 & E27A | | |
| 7-AB4- 17 | Floor Panel - Detail E28 | | |
| 7-AB4- 18 | Floor Panel - Detail E30,E31,E32,E33,E34, E35,E36,E37 | | |
| 7-AB4- 19 | Floor Panel - Detail E38 & E39 | | |
| 7-AB4- 20 | Not Used | | |
| 7-AB4- 21 | Floor Panel - Detail E40 & E45 | | |
| 7-AB4- 22 | Floor Panel - Detail E41 & E46 | | |
| 7-AB4- 23 | Floor Panel - Detail E42 | | |
| 7-AB4- 24 | Floor Panel - Detail E43 | | |
| 7-AB4- 25 | Floor Panel - Detail E44 | | |
| 7-AB4- 26 | Not Used | | |
| 7-AB4- 27 | Not Used | | |
| 7-AB4- 28 | Floor Panel - Detail E47 & E48 | | |
| 7-AB4- 29 | Floor Panel - Detail E49 & E49A | | |
| 7-AB4- 30 | Floor Panel - Detail E50 | | |
| 7-AB4- 31 | Floor Panel - Detail E51A, E51B, E51C | | |
| 7-AB4- 32 | Floor Panel - Detail E52A, E52B, E52C | | |
| 7-AB4- 33 | Floor Panel - Detail E53 | | |
| 7-AB4- 34 | Floor Panel - Detail E54 | | |
| 7-AB4- 35 | Floor Panel - Detail E55 | | |
| 7-AB4- 36 | Floor Panel - Detail E56 | | |
| 7-AB4- 37 | Floor Panel - Detail E57 | | |
| 7-AB4- 38 | Floor Panel - Detail E58,E59,E60 | | |
| 7-AB4- 39 | Floor Panel - Detail E58, E59 | | |

NOTES:

1. The Contractor shall detail all connections, erection aids and all else required for the fabrication, assembly and erection of the pre-fabricated floor panels. Steel deck and power/telephone cell details shall be done by the Contractor for WTC Contract 222.00--all other details by the Contractor for WTC Contract 221.00. Details shall incorporate the geometry requirements and specific detail requirements where indicated in Drawing Book 7. Details shall be proportioned to transmit the loads indicated in Drawing Book 7 and all other loads required for assembly and for erection.

2. The Contractor shall submit details to the Engineer for review prior to performing any work.

LESLIE E. ROBERTSON — No. 34360 — REGISTERED PROFESSIONAL ENGINEER — STATE OF NEW YORK