SKILLING, HELLE, CHRISTIANSEN, ROBERTSON — Structural & Civil Engineers

PROJECT: THE WORLD TRADE CENTER | TITLE: STEEL DECK - INDEX & GEN. NOTES | DATE: 4/ 1/69

REVISIONS

Prin. ed 5-1-69

7-AB5- 1 INDEX & GEN. NOTES
7-AB5- 2 TYPICAL DETAILS A-D
7-AB5- 3 TYPICAL DETAILS E-G
7-AB5- 3.1 TYPICAL DETAIL H
7-AB5- 3.2 TYPICAL DETAIL K
7-AB5- 4 POWER/TELEPHONE DETAILS
7-AB5- 4.1 POWER/TELEPHONE DETAILS
7-AB5- 5 SECTIONS A-DCOD
7-AB5- 6 SECTIONS E-H
7-AB5- 7 SECTIONS J-N
7-AB5- 8 SECTIONS P-T
7-AB5- 8.1 SECTIONS U-X
7-AB5- 8.2 SECTIONS Y, YYGZ
7-AB5- 9 DETAIL K
7-AB5-10 DETAIL M
7-AB5-11 DETAIL N
7-AB5-12 DETAIL P
7-AB5-13 DETAIL Q
7-AB5-14 DETAIL R
7-AB5-15 DETAIL S
7-AB5-16 SUPPORTS
7-AB5-17 DETAIL T
7-AB5-18 DETAIL U
7-AB5-19 DETAIL V&W

GENERAL NOTES.

1. STEEL DECK TO BE 22 GAGE GALV.

2. ALL PLUG WELDS SHALL BE FURNISHED UNDER CONTRACT WTC 223.00 OR CONTRACT WTC 230.00, WHICH EVER IS APPLICABLE.

LICENSED PROFESSIONAL ENGINEER — LESLIE E. ROBERTSON — No. 34360 — STATE OF NEW YORK