SKILLING - HELLE - CHRISTIANSEN - ROBERTSON — Structural & Civil Engineers

PROJECT THE WORLD TRADE CENTER | TITLE POST TENSIONING, GENERAL NOTES & INDEX | DATE 5-1-68

REVISIONS
-3-69
2-3-69
3-3-69
4-1-69
Printed 5-1-69

INDEX

S-AK9-1 General notes & Index
S-AK9-2 Effective prestress force
S-AK9-3.1 Typical details of prestressing tendons
S-AK9-3.2 Schematic Layout of prestressing tendons
S-AK9-3.3 Typical destressing pocket detail
S-AK9-4 Typical sections at sloped slab

General Notes:

1. Concrete in slab shall be fc - 4000 psi minimum at 7 days.
2. Concrete strength at transfer of prestress force to concrete shall be at least 4000 psi.

LICENSED PROFESSIONAL ENGINEER — LESLIE E. ROBERTSON — No. [illegible] — NEW YORK