SKILLING - HELLE - CHRISTIANSEN - ROBERTSON — Structural & Civil Engineers

PROJECT THE WORLD TRADE CENTER | TITLE POST TENSIONING GENERAL NOTES & INDEX | DATE 5-1-68

REVISIONS
-3-69
2-3-69
3-3-69

INDEX

S-AK9-1 General notes & Index.
S-AK9-2 Effective prestress force
S-AK9-3.1 Typical details of prestressing tendons
S-AK9-3.2 Schematic Layout of prestressing tendons
S-AK9-3.3 Typical destressing pocket detail
S-AK9-4 Typical sections at sloped slab.

General Notes:

1. Concrete in slab shall be fc = 4000 psi minimum at 7 days.
2. Concrete strength at transfer of prestress force to concrete shall be at least 4000 psi.

LICENSED PROFESSIONAL ENGINEER
LESLIE E. ROBERTSON
No. 3930
NEW YORK