SKILLING - HELLE - CHRISTIANSEN - ROBERTSON  Structural & Civil Engineers

PROJECT THE WORLD TRADE CENTER | TITLE POST TENSIONING, GENERAL NOTES & INDEX | DATE 5-1-68

REVISIONS

## INDEX


S-AK9-1 General notes & Index
S-AK9-2 Effective prestress force
S-AK9-3.1 Typical details of prestressing tendons
S-AK9-3.2 Schematic Layout of prestressing tendons
S-AK9-3.3 Typical destressing packet detail
S-AK9-4 Typical sections of sloped slab


General Notes:

1. Concrete in slab shall be fc = 4000 psi minimum at 7 days.
2. Concrete strength at transfer of prestress force to concrete shall be at least 4000 psi.

