SKILLING, HELLE, CHRISTIANSEN, ROBERTSON — Structural & Civil Engineers

PROJECT: THE WORLD TRADE CENTER | TITLE: ONE WAY SLAB WITH WWF SCHEDULE | DATE: 5-1-68

REVISIONS

10-21-68

SLAB MARK	SLAB t inch	SLAB TYPE note 1.	BOTTOM REINF'M'T. MAIN REINF. Size	MAIN REINF. Sp'g	TRANSV. REINF. Size	TRANSV. REINF. Sp'g in.	TOP REINFORCEMENT OVER SUPPORTS MAIN WIRES, Ts Size	MAIN WIRES, Ts Sp'g	TRANSV. WIRES Size	TRANSV. WIRES Sp'g	BETWEEN SUPPORTS MAIN WIRES, Tm Size	MAIN WIRES, Tm Sp'g	BETWEEN SUPPORTS TRANSV. WIRES Size	TRANSV. WIRES Sp'g	ADDED TRANSV. AT PNL. ENDS, Te Size	ADDED TRANSV. AT PNL. ENDS, Te Sp'g	REMARKS
L	6"	D	D-0.457	4"	D-0.351	9"	D-0.457	4"	D-0.351	9"	—						
M	6"	C	D-0.498	6"	D-0.351	9"	D-0.498	6"	D-0.351	9"	—						
P	8"	C	D-0.401	6"	D-0.382	8"	D-0.401	6"	D-0.382	8"	—						
Q	6"	D	D-0.457	4"	D-0.351	9"	D-0.457	4"	D-0.351	9"	—						
R	7"	D	D-0.480	3"	D-0.357	9"	D-0.480	3"	D-0.357	9"	—						
T	7"	D	D-0.40	3"	D-0.357	6"	D-0.40	3"	D-0.357	6"	—						
U	6"	C	D-0.415	6"	D-0.415	8"	D-0.415	6"	D-0.415	8"	—						
V	6"	C	D-0.339	6"	D-0.339	8"	D-0.339	6"	D-0.339	8"	—						
W	8"	D	D-0.431	3"	D-0.357	6"	D-0.431	3"	D-0.357	6"	—						
X	6"	D	D-0.484	3"	D-0.456	6"	D-0.484	3"	D-0.456	6"	—						
Y	6"	D	D-0.351	9"	D-0.351	9"	D-0.351	9"	D-0.351	9"	—						
Z	6"	C	D-0.437	6"	D-0.351	9"	D-0.437	6"	D-0.351	9"	—						
P-1	5½"	C	D-0.502	4"	D-0.275	6"	D-0.502	4"	D-0.275	6"	—						
P-2	5½"	C	D-0.455	3"	D-0.275	6"	D-0.455	3"	D-0.275	6"	—						

LICENSED PROFESSIONAL ENGINEER — LESLIE E. ROBERTSON — No. 34360 — UNIVERSITY OF THE STATE OF NEW YORK

Notes:

For notes see 8-JK5-7.1

DESIGNED

DRAWN

REVIEWED

8-JK5-7.2