SKILLING, HELLE, CHRISTIANSEN, ROBERTSON — Structural & Civil Engineers

PROJECT: THE WORLD TRADE CENTER | TITLE: ONE WAY SLAB WITH W.W.F. SCHEDULE | DATE: 12-18-68

REVISIONS
5-5-69

SLAB MARK	SLAB t inch	SLAB TYPE note 1	BOTTOM REINF'M'T. MAIN REINF. Size	MAIN REINF. Spcg.	TRANSV. REINF. Size	TRANSV. REINF. Spcg. in.	TOP REINFORCEMENT OVER SUPPORTS MAIN WIRES Ts Size	MAIN WIRES Ts Spcg.	TRANSV. WIRES Size	TRANSV. WIRES Spcg.	BETWEEN SUPPORTS MAIN WIRES Tm Size	MAIN WIRES Tm Spcg.	BETWEEN SUPPORTS TRANSV. WIRES Size	TRANSV. WIRES Spcg.	ADDED TRANSV. AT PNL ENDS Te Size	ADDED TRANSV. AT PNL ENDS Te Spcg.	REMARKS
S-1	6"	D	D-0.492	4"	D-0.38	9"	D-0.492	4"	D-0.38	9"	—						
S-2	7	D	D-0.450	3	D-0.38	9	D-0.450	3	D-0.38	9	—						
S-3	8	D	D-0.492	3	D-0.383	8	D-0.492	3	D-0.383	8	—						
S-4	8	D	D-0.438	4	D-0.383	8	D-0.438	4	D-0.383	8	—						
S-5	8	D	D-0.438	4	D-0.383	8	D-0.438	4	D-0.383	8	—						
S-6	7	D	D-0.497	5	D-0.38	9	D-0.497	5	D-0.38	9	—						
S-7	7	D	D-0.468	4	D-0.38	9	D-0.468	4	D-0.38	9	—						
S-8	6	D	D-0.459	4	D-0.38	9	D-0.459	4	D-0.38	9	—						
S-9	6	D	D-0.494	5	D-0.38	9	D-0.494	5	D-0.38	9	—						
S-10	6	D	D-0.475	5	D-0.38	9	D-0.475	5	D-0.38	9	—						
S-11	6	D	D-0.449	4	D-0.437	6	D-0.449	4	D-0.437	6	—						
S-14	6	D	D-0.464	3	D-0.38	9	D-0.464	3	D-0.38	9	—						
S-15	6	D	D-0.357	4	D-0.357	4	D-0.357	4	D-0.357	4	—						
S-16	6	D	D-0.357	4	D-0.357	4	D-0.357	4	D-0.557	4	—						
S-17	8	D	D-0.500	4	D-0.437	6	D-0.500	4	D-0.437	6	—						
S-18	8	D	D-0.495	3	D-0.383	8	D-0.495	3	D-0.383	8	—						

Note
For notes see 8-JK5-7.1

LICENSED PROFESSIONAL ENGINEER — LESLIE E. ROBERTSON — No. 34300 — UNIVERSITY OF THE STATE OF NEW YORK

DESIGNED
DRAWN S.C.
REVIEWED J.M. & E.L.

8-JK5-7.3