WORTHINGTON, SKILLING, HELLE & JACKSON — Civil & Structural Engineers

PROJECT: THE WORLD TRADE CENTER | TITLE: COLUMN SCHEDULE | DATE: 5-15-67

REVISIONS
2-9-68

	J2-8	J2-9	J2-10	J2-11	J2-12	J2-13	J2-14
El. 332'							
El. 310'	*	*	*	*	*	*	*
El. 294'	14 WF 176 (Fy=50)	14 WF 176 (Fy=42)	14 WF 176 (Fy=50)	14 WF 167 (Fy=50)	14 WF 167 (Fy=50)	14 WF 167 (Fy=50)	14 WF 167 (Fy=50)
El. 284'							
El. 274'							
El. 264'	14 WF 193 (Fy=50)	14 WF 342 (Fy=50)	14 WF 342 (Fy=50)	14 WF 342 (Fy=50)	14 WF 342 (Fy=50)	14 WF 342 (Fy=50)	14 WF 193 (Fy=50)
El. 253		▲ 14 WF 342 (Fy=50)	▲ 14 WF 342 (Fy=50)	▲ 14 WF 342 (Fy=50)	▲ 14 WF 342 (Fy=50)	▲ 14 WF 342 (Fy=50)	
Top of base Pl		El. 243'-6"	El. 243'-6"	El. 243'-6"	El. 243'-6"	El. 243'-6"	
Base Plate		45 × 5 × 4'-1"	45 × 5 × 4'-1"	45 × 5 × 4'-1"	45 × 5 × 4'-1"	45 × 5 × 4'-1"	

LICENSED PROFESSIONAL ENGINEER — LESLIE E. ROBERTSON — No. 34360 — UNIVERSITY OF THE STATE OF NEW YORK

* Provide proper splice pls., bolt holes & finished col. top for future columns. Use upper col. one size smaller except as shown.
▲ See detail on 10-JK4-3 and 4.
■ Splice 3" above slab. See note on 10-JK2-2.
● See detail on 10-JK2-30.

10-J1-6