WORTHINGTON, SKILLING, HELLE & JACKSON — Civil & Structural Engineers

PROJECT: THE WORLD TRADE CENTER | TITLE: COLUMN SCHEDULE | DATE: 5-15-67

REVISIONS
2-9-68
4-5-68
5-1-68
6-17-68

	J3-1	J3-2	J3-3	J3-4	J3-5	J3-6	J3-7
El. 332'			Det. 104 10-JK2-7	See Detail 1-1 on 10-JK2-36	10-JK2-17	10-JK2-17	10-JK2-17
El. 310'	*	*					
El. 294'	14 WF 158 (Fy=50)	14 WF 127 (Fy=50)	14 WF 342 (Fy=50)	14 WF 287 (Fy=50)	14 WF 314 (Fy=50)	14 WF 314 (Fy=50)	14 WF 314 (Fy=50)
El. 284'							
El. 274'				Truss JT-2 See dwg. 11-VI-3			
El. 264'	14 WF 314 (Fy=50)	14 WF 246 (Fy=50)	14 WF 730 (Fy=46)		14 WF 426 (Fy=50)	14 WF 398 (Fy=50)	14 WF 398 (Fy=50)
El. 253	▲ 14 WF 314 (Fy=50)	▲ 14 WF 246 (Fy=50)	▲ 14 WF 730 (Fy=46)		14 WF 426 (Fy=50)	▲ 14 WF 398 (Fy=50)	▲ 14 WF 398 (Fy=50)
Top of base Pl	El. 249'	El. 249'	El. 244'		El. 241'	El. 241'	El. 241'
Base Plate	45 × 4⅝ × 4'-0"	41 × 4⅛ × 3'-8"	60 × 7¼ × 5'-7"		63 × 7¾ × 5'-7"	62 × 7½ × 5'-6"	62 × 7½ × 5'-6"

* Provide proper splice pls., bolt holes & finished col. top for future columns. Use upper col. one size smaller except as shown.
▲ See detail on 10-JK4-3 and 4.
■ Splice 3" above slab. See note on 10-JK2-2.
● See detail on 10-JK2-30.

10-J1-12

LICENSED PROFESSIONAL ENGINEER LESLIE E. ROBERTSON No. 34360 UNIVERSITY OF THE STATE OF NEW YORK

A