WORTHINGTON, SKILLING, HELLE & JACKSON — Civil & Structural Engineers

PROJECT: THE WORLD TRADE CENTER | TITLE: COLUMN SCHEDULE | DATE: 5-15-67

REVISIONS
2-9-68
2-29-68
4-5-68
5-1-68
6-7-68
6-17-68

	J3-8	J3-9	J3-10	J3-11	J3-12	J3-13	J3-14
El. 332'	10-JK2-17	10-JK2-17	Det. 104 10-JK2-7				
El. 310'				*	*	R Girder; 14WF103 (Fy=50) *	
El. 294'	14WF320 (Fy=50)	14WF342 (Fy=50)	Splice, see Det. on 10-JK2-36; 14WF370 (Fy=50)	14WF136 (Fy=50)	14WF136 (Fy=50)	12-JK2-118A; 14WF103 (Fy=50)	
El. 284'							
El. 274'			Part of Truss JT-3 See dwg. 11-J1-4				Truss JT-4
El. 264'	14WF426 (Fy=50)	14WF426 (Fy=50)	14WF53 (Fy=42)	See detail on 12-JK2-52	14WF158 (Fy=50)	See Det. 10-JK2-35	
El. 253	▲ 14WF426 (Fy=50)	▲ 14WF426 (Fy=50)	See detail on 10-JK2-35	14WF287 (Fy=50)			14WF158 (Fy=50)
Top of base Pl	El. 241'	El. 241'		El. 243'-6"			El. 243'-6"
Base Plate	63 × 7¾ × 5'-7"	63 × 7¾ × 5'-7"		43 × 4¾ × 3'-9"			See dwg 10-JK32A

LICENSED PROFESSIONAL ENGINEER LESLIE E. ROBERTSON No. 34360 UNIVERSITY OF THE STATE OF NEW YORK

* Provide proper splice pls., bolt holes & finished col. top for future columns. Use upper col. one size smaller except as shown.
▲ See detail on 10-JK4-3 and 4.
■ Splice 3" above slab. See note on 10-JK2-2.
● See detail on 10-JK2-30.

10-J1-13

A