WORTHINGTON, SKILLING, HELLE & JACKSON — Civil & Structural Engineers

PROJECT: THE WORLD TRADE CENTER | TITLE: COLUMN SCHEDULE | DATE: 5-15-67

REVISIONS
2-9-68
4-5-68
5-1-68
6-17-68

	J4-8	J4-9	J4-10	J4-11	J4-12	J4-12A	J4-13
El. 332'	10-JK2-17	10-JK2-17	10-JK2-17	16-JK2-17	10-JK2-17		10-JK2-17
El. 310'							
El. 294'	14WF264 (Fy=50)	14WF264 (Fy=50)	Truss JT-3 See dwg. J1-J4 Splice, See Det. 3 10-JK2-36 14WF264 (Fy=50)	14WF314 (Fy=50)	14WF314 (Fy=50)		14WF320 (Fy=50)
El. 284'							
El. 274'	14WF370 (Fy=50)	14WF370 (Fy=50)		14WF426 (Fy=50)	14WF342 (Fy=50)		14WF342 (Fy=50)
El. 264'							
El. 253	▲ 14WF370 (Fy=50)	▲ 14WF370 (Fy=50)	Splice, See Det. 4 10-JK2-36 ▲ 14WF370 (Fy=50)	▲ 14WF426 (Fy=50)			
Top of base Pl	El. 241'	El. 241'	El. 241'	El. 241'		El. 243'-6" 14WF426 (Fy=50)	
Base Plate	60 × 7¼ × 5'-3"	60 × 7¼ × 5'-3"	60 × 7¼ × 5'-3"	63 × 7¾ × 5'-7"		56 × 6½ × 5'-0"	

* Provide proper splice pls., bolt holes & finished col. top for future columns. Use upper col. one size smaller except as shown.
▲ See detail on 10-JK4-3 and 4.
■ Splice 3" above slab. See note on 10-JK2-2.
● See detail on 10-JK2-30.

10-J1-18

LICENSED PROFESSIONAL ENGINEER — LESLIE E. ROBERTSON — No. 34360 — UNIVERSITY OF THE STATE OF NEW YORK

A