WORTHINGTON, SKILLING, HELLE & JACKSON — Civil & Structural Engineers

PROJECT: THE WORLD TRADE CENTER | TITLE: COLUMN SCHEDULE | DATE: 5-15-67

REVISIONS
5-1-68
6-28-68
4-4-69

	J4-14		J4-16	J4-17		J4-19	J4-20
El. 332'							
El. 310'							Bott. of ℄ Girder
El. 290'	Part of Truss JT-5		Part of Truss JT-5				14 WF 550 (Fy=50)
El. 274'	Part of Truss JT-4 14 WF 287 (Fy=50)		Det. 7 10-JK2-36 14 WF 550 (Fy=50				
El. 264'			14 WF 605 +℄ 14×3 (B.S.) (Fy=46)			14 WF 87 (Fy=42)	14 WF 550 (Fy=50)
Top of base ℄	Splice, see Det. 5 10-JK2-36 18×17 I 2 ℄s 17×4 1 ℄ 10×2½ (Fy=50) El. 243'-4"		▲ 14 WF 605 +℄ 14×3 (B.S.) (Fy=46) El. 243'-4"	14 WF 211 (Fy=50) El. 243'-4"			
Base Plate	67×8×6'-1"		69×8¾×6'-9"	40×4×3'-7"			

* Provide proper splice pls., bolt holes & finished col. top for future columns. Use upper col. one size smaller except as shown.
▲ See detail on 10-JK4-3 and 4..
■ Splice 3" above slab. See note on 10-JK2-2.
● See detail on 10-JK2-30.

LICENSED PROFESSIONAL ENGINEER — LESLIE E. ROBERTSON — No. 34260 — UNIVERSITY OF THE STATE OF NEW YORK

DRAWN S.C.
REVIEWED E.L.

10-J1-19

B