WORTHINGTON, SKILLING, HELLE & JACKSON — Civil & Structural Engineers

PROJECT: THE WORLD TRADE CENTER | TITLE: COLUMN SCHEDULE | DATE: 5-15-67

REVISIONS
5-1-68
6-7-68

	J4-21	J4-22
El. 332'		
El. 310'		* 14 WF 211 (Fy=50)
El. 290'		
El. 274'		
El. 264'		
Top of base Pl	El Bott of Pl Girder — 14 WF 550 (Fy=50) — El. 243'-4"	14 WF 398 (Fy=50) — El. 243'-4"
Base Plate	67 × 8 × 6'-1"	55 × 6½ × 4'-11"

* Provide proper splice pls., bolt holes & finished col. top for future columns. Use upper col. one size smaller except as shown.
▲ See detail on 10-JK4-3 and 4..
■ Splice 3" above slab. See note on 10-JK2-2.
● See detail on 10-JK2-30.

10-J1-20

LICENSED PROFESSIONAL ENGINEER — LESLIE E. ROBERTSON — No. 34280 — UNIVERSITY OF THE STATE OF NEW YORK

B