WORTHINGTON, SKILLING, HELLE & JACKSON — Civil & Structural Engineers

PROJECT: THE WORLD TRADE CENTER | TITLE: COLUMN SCHEDULE | DATE: 5-15-67

REVISIONS
—
9-20-67
11-8-67

J10-51

El. 332'

El. 310'

Street level

El. 294'

14WF87 (Fy=50)

El. 284'

El. 274'

14WF95 (Fy=50)

El. 264'

14WF127 (Fy=50)

El. 253

Top of base Pl at El. 241'

Base Plate — 32 × 3 × 2'-9"

LICENSED PROFESSIONAL ENGINEER
LESLIE E. ROBERTSON
No. 34360
OF THE STATE OF NEW YORK

* Provide proper splice pls., bolt holes & finished col. top for future columns. Use upper col. one size smaller except as shown.
▲ See detail on 10-JK4-3 and 4.
■ Splice 3" above slab. See note on 10-JK2-2.
● See detail on 10-JK2-30.

10-J1-47