WORTHINGTON, SKILLING, HELLE & JACKSON — Civil & Structural Engineers

PROJECT: THE WORLD TRADE CENTER | TITLE: COLUMN SCHEDULE | DATE: 5-15-67

REVISIONS
- 10-20-67
- 11-8-67

	J11-1	J11-2	J11-3	J11-4	J11-5	J11-6	J11-7
El. 332'							
El. 310'	●	●	●	●	●	●	●
El. 294'	14 WF 426 (Fy=50)	14 WF 398 (Fy=50)	14 WF 398 (Fy=50)	14 WF 398 (Fy=50)	14 WF 398 (Fy=50)	14 WF 398 (Fy=50)	14 WF 150 (Fy=50)
El. 284'							
El. 274'	+	+	+	+	+	+	+
El. 264'	14 WF 455 (Fy=50)	14 WF 455 (Fy=50)	14 WF 455 (Fy=50)	14 WF 455 (Fy=50)	14 WF 455 (Fy=50)	14 WF 455 (Fy=50)	14 WF 167 (Fy=50)
El. 253	▲	▲	▲	▲	▲	▲	▲
Top of base Pl at El. 241'	14 WF 550 (Fy=50)	14 WF 500 (Fy=50)	14 WF 500 (Fy=50)	14 WF 500 (Fy=50)	14 WF 500 (Fy=50)	14 WF 500 (Fy=50)	14 WF 237 (Fy=50)
Base Plate	$72 \times 8\frac{3}{4} \times 6'\text{-}10''$	$72 \times 8\frac{3}{4} \times 6'\text{-}10''$	$72 \times 8\frac{3}{4} \times 6'\text{-}10''$	$72 \times 8\frac{3}{4} \times 6'\text{-}10''$	$72 \times 8\frac{3}{4} \times 6'\text{-}10''$	$72 \times 8\frac{3}{4} \times 6'\text{-}10''$	$44 \times 4\frac{1}{2} \times 3'\text{-}10''$

LICENSED PROFESSIONAL ENGINEER — LESLIE E. ROBERTSON — No. 34360 — UNIVERSITY OF THE STATE OF NEW YORK

* Provide proper splice pls., bolt holes & finished col. top for future columns. Use upper col. one size smaller except as shown.
▲ See detail on 10-JK4-3 and 4.
■ Splice 3" above slab. See note on 10-JK2-2.
● See detail on 10-JK2-30.

10-J1-48