WORTHINGTON, SKILLING, HELLE & JACKSON — Civil & Structural Engineers

PROJECT: THE WORLD TRADE CENTER | TITLE: COLUMN SCHEDULE | DATE: 5-15-67

REVISIONS
10-20-67
11-8-67

	J13-1	J13-2	J13-3	J13-4	J13-5	J13-6
El. 332'						
El. 310'	El. 308'-10" ●					
El. 294'	14 WF 167 (Fy=50)	14 WF 95 (Fy=50)	14 WF 95 (Fy=50)	14 WF 87 (Fy=50)	14 WF 87 (Fy=50)	14 WF 95 (Fy=50)
El. 284'						
El. 274'	14 WF 176 (Fy=50)	14 WF 111 (Fy=50)	14 WF 111 (Fy=50)	14 WF 111 (Fy=50)	14 WF 103 (Fy=50)	14 WF 103 (Fy=50)
El. 264'	▲	▲	▲	▲	▲	▲
El. 253	14 WF 219 (Fy=50)	14 WF 158 (Fy=50)	14 WF 158 (Fy=50)	14 WF 142 (Fy=50)	14 WF 142 (Fy=50)	14 WF 127 (Fy=50)
Top of base Pl at El. 241'						
Base Plate	46 × 4¾ × 4'-0"	40 × 3¾ × 3'-2"	40 × 3¾ × 3'-2"	38 × 3½ × 2'-11"	38 × 3½ × 2'-11"	34 × 3⅜ × 3'-1"

* Provide proper splice pls., bolt holes & finished col. top for future columns. Use upper col. one size smaller except as shown.
▲ See detail on 10-JK4-3 and 4.
■ Splice 3" above slab. See note on 10-JK2-2.
● See detail on 10-JK2-30.

LICENSED PROFESSIONAL ENGINEER — LESLIE E. ROBERTSON — No. 34360 — UNIVERSITY OF THE STATE OF NEW YORK

10-J1-5