WORTHINGTON, SKILLING, HELLE & JACKSON — CIVIL & STRUCTURAL ENGINEERS

PROJECT: THE WORLD TRADE CENTER | TITLE: COLUMN SCHEDULE | DATE: 5-15-67

REVISIONS
10-20-67
11-8-67

	J14-1	J14-2	J14-3	J14-4	J14-5	J14-6
El. 332'						
El. 310'						
Street level						
El. 294'	14 WF 103 (Fy=50)		14 WF 150 (Fy=50)	14 WF 142 (Fy=50)	14 WF 211 (Fy=50)	14 WF 61 (Fy=50)
El. 284'						
El. 274'	14 WF 103 (Fy=50)	14 WF 74 (Fy=50)	14 WF 176 (Fy=50)	14 WF 167 (Fy=50)	14 WF 228 (Fy=50)	14 WF 74 (Fy=50)
El. 264'						
El. 253	14 WF 119 (Fy=50)	14 WF 111 (Fy=50)	14 WF 264 (Fy=50)	14 WF 246 (Fy=50)	14 WF 320 (Fy=50)	14 WF 111 (Fy=50)
Top of base Pl at El. 241'						
Base plate	32×3×2'-9"	32×3×2'-9"	48×5¼×4'-4"	48×5¼×4'-2"	50×5×4'-0"	32×3×2'-9"

* Provide proper splice pls., bolt holes & finished col. top for future columns. Use upper col. one size smaller except as shown.
▲ See detail on 10-JK4-3 and 4.
■ Splice 3" above slab. See note on 10-JK2-2.
● See detail on 10-JK2-30.

10-J1-56

LICENSED PROFESSIONAL ENGINEER — LESLIE E. ROBERTSON — No. 34360 — UNIVERSITY OF THE STATE OF NEW YORK

A