WORTHINGTON, SKILLING, HELLE & JACKSON — Civil & Structural Engineers

PROJECT: THE WORLD TRADE CENTER | TITLE: COLUMN SCHEDULE | DATE: 5-15-67

REVISIONS
- 10-20-67
11-8-67

	J19-1	J19-2	J19-3	J19-4	J19-5
El. 332'					
El. 310'					
Street level					
El. 294'	14 WF 61 (Fy=50)	14 WF 87 (Fy=50)	14 WF 119 (Fy=50)	14 WF 167 (Fy=50)	14 WF 87 (Fy=50)
El. 284'					
El. 274'	⊕	⊕	⊕	⊕	⊕
El. 264'	14 WF 68 (Fy=50)	14 WF 111 (Fy=50)	14 WF 142 (Fy=50)	14 WF 202 (Fy=50)	14 WF 103 (Fy=50)
El. 253	▲ 14 WF 95 (Fy=50)	▲ 14 WF 158 (Fy=50)	▲ 14 WF 219 (Fy=50)	▲ 14 WF 314 (Fy=50)	▲ 14 WF 150 (Fy=50)
Top of base Pl at El. 241'					
Base Plate	32 × 2 3/4 × 2'-5"	38 × 3 3/4 × 3'-4"	46 × 4 3/4 × 4'-2"	48 × 5 1/4 × 4'-4"	38 × 3 7/8 × 3'-5"

* Provide proper splice pls., bolt holes & finished col. top for future columns. Use upper col. one size smaller except as shown.
▲ See detail on 10-JK4-3 and 4.
■ Base 3" above slab. See note on 10-JK2-2.
● See detail on 10-JK2-30.

10-J1-68

RICHARD PROFESSIONAL ENGINEER LESLIE E. ROBERTSON No. 34360 UNIVERSITY OF THE STATE OF NEW YORK

A