WORTHINGTON, SKILLING, HELLE & JACKSON — Civil & Structural Engineers

PROJECT: THE WORLD TRADE CENTER | TITLE: COLUMN SCHEDULE | DATE: 5-15-67

REVISIONS
- 10-20-67
- 11-8-67
- 1-13-69

| | J23-1 | J23-2 | J23-3 | J23-4 | J23-5 | J23-6 | J23-7 |
|---|---|---|---|---|---|---|---|
| El. 332' | | | | | | | |
| El. 310' | | | | | 14 WF 87 (Fy=50) | 14 WF 228 (Fy=50) | 14 WF 111 (Fy=50) |
| Street level | | | | | | | |
| El. 294' | 14 WF 68 (Fy=50) | 14 WF 119 (Fy=50) | 14 WF 167 (Fy=50) | 14 WF 87 (Fy=50) | | | |
| El. 284' | | | | | | | |
| El. 274' | | | | | | | |
| El. 264' | 14 WF 74 (Fy=50) | 14 WF 142 (Fy=50) | 14 WF 202 (Fy=50) | 14 WF 111 (Fy=50) | | | |
| El. 253 | ▲ 14 WF 103 (Fy=50) | ▲ 14 WF 219 (Fy=50) | ▲ 14 WF 314 (Fy=50) | ▲ 14 WF 158 (Fy=50) | | | |
| Top of base Pl at El. 241' | | | | | | | |
| Base Plate | 32 × 3 × 2'-9" | 46 × 4¾ × 4'-2" | 54 × 5½ × 4'-3" | 38 × 3¾ × 3'-4" | | | |

★ Provide proper splice pls., bolt holes & finished col. top for future columns. Use upper col. one size smaller except as shown.
▲ See detail on 10-JK4-3 and 4.
■ Splice 3" above slab. See note on 10-JK2-2.
● See detail on 10-JK2-30.

LICENSED PROFESSIONAL ENGINEER — LESLIE E. ROBERTSON — No. 34960 — STATE OF NEW YORK

DRAWN S.C.
REVIEWED R.T. & E.L.

10-J1-75

A