WORTHINGTON, SKILLING, HELLE & JACKSON — Civil & Structural Engineers

PROJECT: THE WORLD TRADE CENTER | TITLE: COLUMN SCHEDULE | DATE: 5-15-67

REVISIONS
5-1-68
6-7-68
10-15-68

	J72-4	J72-5	J72-6	J72-7
El. 332'				
El. 310'				
El. 290'	2-Girder 14 WF 264 (Fy=50)	14 WF 228 (Fy=50)	14 WF 237 (Fy=50)	Det. 1 / 10-JK2-41 14 WF 211 (Fy=50)
El. 279'3"	⊗	⊗	⊗	Temp. bracing
El. 264'	14 WF 550 (Fy=50) ▲	Temp. bracing	Temp. bracing	20×12 I 2 PL 3"×12×2¾ 1 PL 14½×1½ (Fy=50)
El. 253	14 WF 550 (Fy=50)	20×12 II 2 PL 3"×12×5 2 PL 3"×10×4 (Fy=50)	20×12 II 2 PL 3"×12×5 2 PL 3"×10×4 (Fy=50)	See detail on 10-JK2-35B 14 WF 342 (Fy=50)
Top of Base Pl.	El. 243'-4"	El. 243'-4"	El. 243'-4"	El. 243'-4"
Base Plate	57×7×5'-2"	53×7×5'-0"	57×7×5'-1"	53×6¼×4'-9"

✱ Provide proper splice pls., bolt holes & finished col. top for future columns. Use upper col. one size smaller except as shown.
▲ See detail on 10-JK4-3 and 4.
■ Splice 3" above slab. See note on 10-JK2-2.
● See detail on 10-JK2-30.
⊗ Splice detail, see 10-JK2-35A

10-J1-84

LICENSED PROFESSIONAL ENGINEER — LESLIE E. ROBERTSON — NO. 54260 — UNIVERSITY OF THE STATE OF NEW YORK