WORTHINGTON, SKILLING, HELLE & JACKSON — Civil & Structural Engineers

PROJECT THE WORLD TRADE CENTER | TITLE COLUMN SCHEDULE | DATE 5-15-67

REVISIONS
5-1-68
6-7-68
10-15-68

	J74-2	J74-3	J74-4	J74-5	J74-6		
El. 332'							
El. 310'							
El. 290'			14WF314 (Fy=50)	14WF264 (Fy=50)	Det. 5 / 10-JK2-41; 14WF264 (Fy=50)		
El. 279'-3"			⊗	⊗			
El. 274'							
El. 264'	Bott. of R Girder; 14WF550 (Fy=50)	Bott. of R Girder; 14WF665 +R 15×3 (B.S.) (Fy=46)	Temp. bracing	Temp. bracing	Temp. bracing; 20×12 I, 2PL 12×3, 1PL 14×2; (Fy=50)		
El. 253							
Top of Base Pl.	El. 243'-4"	El. 243'-4" Temp. bracing	El. 243'-4" 20×12 II, 2PL 12×5, 2PL 10×4 (Fy=50)	El. 243'-4" 20×12 II, 2PL 12×5, 2PL 10×4 (Fy=50)	El. 243'-4" See detail on 10-JK2-35B; 14WF398 (Fy=50)		
Base Plate	59×7×5'-5"	74×9×7'-4"	64×8¾×5'-9"	57×7¾×5'-1"	57×7×5'-1"		

14WF550 (Fy=50)
14WF665 +R 15×3 (B.S.) (Fy=46)

✱ Provide proper splice pls., bolt holes & finished col. top for future columns. Use upper col. one size smaller except as shown.
▲ See detail on 10-JK4-3 and 4.
■ Splice 3" above slab. See note on 10-JK2-2.
● See detail on 10-JK2-30.
⊗ Splice detail, see 10-JK2-35A.

10-J1-90

LICENSED PROFESSIONAL ENGINEER — LESLIE E. ROBERTSON — NO. 54380 — STATE OF NEW YORK