WORTHINGTON, SKILLING, HELLE & JACKSON — Civil & Structural Engineers

PROJECT: THE WORLD TRADE CENTER | TITLE: COLUMN SCHEDULE | DATE: 5-15-67

REVISIONS
10-20-67
11-8-67
12-23-71
1-15-72
11-27-72

	K31-1	K31-2	K31-3	K31-4	K31-5	K31-6	K31-7
El. 332'							12-JK2-181
El. 310'			■ See Dwg. Book 13		■ See D.B. 13	■ See D.B. 13	■ 14 WF 370 (Fy=50)
Street level	● 14 WF 111 (Fy=50)	● 14 WF 184 (Fy=50)	14 WF 264 (Fy=50)		14 WF 426 (Fy=50)	See 19-1053 for new cover PL	14 WF 398 (Fy=50)
El. 294'							
El. 284'							
El. 274'							
El. 264'	14 WF 127 (Fy=50)	14 WF 246 (Fy=50)	14 WF 320 (Fy=50)				
El. 253	▲ 14 WF 202 (Fy=50)	▲ 14 WF 370 (Fy=50)	▲ 14 WF 455 (Fy=50)	14 WF 84 (Fy=50)	14 WF 320 + PL 2⅛ × 3 (B.S.) (Fy=42)	14 WF 320 + PL 2⅜ × 2⅛ (B.S.) (Fy=42)	14 WF 320 + PL 2⅜ × 2⅛ (B.S.) (Fy=42)
Top of base PL at El. 241'							
Base Plate	40 × 3¾ × 3'-1"	54 × 5⅞ × 4'-3"	62 × 7 × 4'-9"	20 × 2⅛ × 2'-4"	60 × 7 × 5'-6"	60 × 7 × 5'-5"	60 × 7 × 5'-6"

* Provide proper splice pls., bolt holes & finished col. top for future columns. Use upper col. one size smaller except as shown.
▲ See detail on 10-JK4-3 and 4.
■ Splice 3" above slab. See note on 10-JK2-2.
● See detail on 10-JK2-30.

LICENSED PROFESSIONAL ENGINEER — LESLIE E. ROBERTSON — No. 34360 — UNIVERSITY OF THE STATE OF NEW YORK

DRAWN S.C.
REVIEWED E.L.

10-K1-207