WORTHINGTON, SKILLING, HELLE & JACKSON — Civil & Structural Engineers

PROJECT: THE WORLD TRADE CENTER | TITLE: COLUMN SCHEDULE | DATE: 5-15-67

REVISIONS
10-20-67
11-8-67
12-23-71
1-15-72
11-27-72

	K35-1	K35-2	K35-3	K35-4	K-35-5	K35-6	K35-7
El. 332'							12-JK2-181
El. 310'		* (See Dwg. Book 13)		* (See DB 13)	* (See DB 13)	* (See DB. 13.)	* 14 WF 264 (Fy=50)
Street level	14 WF 142 (Fy=50)	14 WF 158 (Fy=50)		See 19-1053 for new cover pl. 14 WF 264 (Fy=50)	See 19-1053 for new cover pl. 14 WF 426 (Fy=50)	See 19-1053 for new cover pl. 14 WF 398 (Fy=50)	14 WF 264 (Fy=50)
El. 294'							
El. 284'							
El. 274'							
El. 264'	14 WF 176 (Fy=50)	14 WF 176 (Fy=50)			14 WF 730 (Fy=46)		
El. 253	▲ 14 WF 314 (Fy=50)	▲ 14 WF 264 (Fy=50)	14 WF 78 (Fy=50)		14 WF 320 + PL 23 × 2 7/8 (B.S.) (Fy=42)	14 WF 320 + PL 23 × 2 7/8 (B.S.) (Fy=42)	14 WF 730 (Fy=46)
Top of base Pl at El. 241'							
Base Plate	46 × 4 3/4 × 4'-0"	46 × 4 1/2 × 3'-10"	20 × 2 1/8 × 2'-4"	54 × 5 7/8 × 4'-9"	60 × 7 × 5'-5"	60 × 7 × 5'-5"	54 × 5 7/8 × 4'-9"

* Provide proper splice pls., bolt holes & finished col. top for future columns. Use upper col. one size smaller except as shown.
▲ See detail on 10-JK4-3 and 4.
■ Splice 3" above slab. See note on 10-JK2-2
● See detail on 10-JK2-30.

LICENSED PROFESSIONAL ENGINEER — LESLIE E. ROBERTSON — No. 34360 — UNIVERSITY OF THE STATE OF NEW YORK

DRAWN S.C.
REVIEWED E.L.

10-K1-211