WORTHINGTON, SKILLING, HELLE & JACKSON — Civil & Structural Engineers

PROJECT: THE WORLD TRADE CENTER | TITLE: COLUMN SCHEDULE | DATE: 5-15-67

REVISIONS
- 10-20-67
- 11-8-67
- 6-7-68
- 12-3-68
- 10-14-69

	K35-8	K35-9	K35-10	K35-11	K35-12		
El. 332'	14 WF 150 (Fy=50)	14 WF 167 (Fy=50)	14 WF 95 (Fy=50)				
El. 310'	Remove existing splice Pls attached to lower column and install new butt Pl similar to detail on 10-JK2-7 (reversed pos.)		*				
El. 294	14 WF 127 (Fy=50)	14 WF 127 (Fy=50)	14 WF 127 (Fy=50)	14 WF 61 (Fy=50)	14 WF 150 (Fy=50)		
El. 284'							
El. 279'-3"							
El. 274'							
El. 264'	14 WF 398 (Fy=50)	14 WF 398 (Fy=50)	14 WF 398 (Fy=50)	14 WF 237 (Fy=50)	14 WF 237 (Fy=50)		
El. 257'-0"							
El. 253							
Top of base Pl at El. 241'							
Base Plate	42 × 4¼ × 3'-8"	42 × 4¼ × 3'-8"	40 × 3¾ × 3'-1"	32 × 2¾ × 2'-7"	46 × 5¼ × 4'-1"		

* Provide proper splice pls., bolt holes & finished col. top for future columns. Use upper col. one size smaller except as shown.
▲ See detail on 10-JK4-3 and 4.
■ Splice 3" above slab. See note on 10-JK2-2.
● See detail on 10-JK2-30.

LICENSED PROFESSIONAL ENGINEER — LESLIE E. ROBERTSON — No. 34360 — UNIVERSITY OF THE STATE OF NEW YORK

DRAWN S.C.
REVIEWED E.L.

10-K1-212

A