WORTHINGTON, SKILLING, HELLE & JACKSON — Civil & Structural Engineers

PROJECT: THE WORLD TRADE CENTER | TITLE: COLUMN SCHEDULE | DATE: 5-15-67

REVISIONS
9-20-68

| | K38-1 | K38-2 | | | | | |
|---|---|---|---|---|---|---|---|
| El. 332' | | | | | | | |
| El. 310' | | | | | | | |
| El. 294' | | 14WF119 (Fy=50) | 14WF342 (Fy=50) | | | | |
| El. 284' | | | | | | | |
| El. 279'-3" | | | | | | | |
| El. 274' | | | | | | | |
| El. 264' | | 14WF127 (Fy=50) | 14WF264 (Fy=50) | | | | |
| El. 253 | | | | | | | |
| Top of base Pl at El. 241' | | | | | | | |
| Base Plate | 35 x 3 3/8 x 2'-11" | 41 x 4 1/4 x 3'-5" | | | | | |




* Provide proper splice pls., bolt holes & finished col. top for future columns. Use upper col. one size smaller except as shown.
▲ See detail on 10-JK4-3 and 4.
■ Splice 3" above slab. See note on 10-JK2-2.
● See detail on 10-JK2-30.

10-K1-218