WORTHINGTON, SKILLING, HELLE & JACKSON — Civil & Structural Engineers

PROJECT: THE WORLD TRADE CENTER | TITLE: COLUMN SCHEDULE | DATE: 5-15-67

REVISIONS
9-20-68
12-3-68
2-4-69
2-11-69
10-14-69
12-23-71
11-27-72

	K41-8	K41-9	K41-10	K41-11
El. 332'				
El. 310'	* 14 WF 150 (Fy=50)	* 14 WF 167 (Fy=50)	■ See Dwg Book 13	
El. 294'	14 WF 246 (Fy=50)	14 WF 287 (Fy=50)	Add'l Cover Pls See 19-K-1053 14 WF 136 (Fy=50)	14 WF 78 (Fy=50)
El. 284'				
El. 274'	14 WF 314 (Fy=50)		14 WF 237 (Fy=50)	
El. 264'		14 WF 605 (Fy=42)		14 WF 87 (Fy=50)
El. 253'				
Top of base Pl ●	El. 241'-0"	El. 241'-0"	El. 241'-0"	El. 235'-5 1/8"
Base Plate	47 x 5 1/8 x 3'-11"	47 x 5 1/8 x 3'-11"	47 x 6 1/8 x 3'-11"	33 x 3 1/8 x 2'-9"

* Provide proper splice pls., bolt holes & finished col. top for future columns. Use upper col. one size smaller except as shown.
▲ See detail on 10-JK4-3 and 4.
■ Splice 3" above slab. See note on 10-JK2-2.
● See detail on 10-JK2-30

LICENSED PROFESSIONAL ENGINEER — LESLIE E. ROBERTSON — No. 34360 — UNIVERSITY OF THE STATE OF NEW YORK

[redacted]

10-K1-222