WORTHINGTON, SKILLING, HELLE & JACKSON — Civil & Structural Engineers

PROJECT: THE WORLD TRADE CENTER | TITLE: COLUMN SCHEDULE | DATE: 5-15-67

REVISIONS
3-1-69
3-12-69
3-21-69
10-23-69
11-27-72

	K47-1	K47-2	K47-3	K47-4	K47-5	K47-6	K47-7
El. 332'							
El. 310'		* See Dwg Book 13	* See D.B. 13	* See D.B. 13	* See D.B. 13	* See D.B. 13	* See D.B. 13
Street level							
El. 294'	14 WF 136 (Fy=50)	14 WF 455 (Fy=50)	14 WF 320 + PL 23×3 (B.S.) (Fy=42)	14 WF 320 + PL 23×2⅞ (B.S.) (Fy=42)	14 WF 398 (Fy=50)	14 WF 228 (Fy=50)	14 WF 211 (Fy=50)
El. 284'							
El. 274'	14 WF 193 (Fy=50)	14 WF 500 (Fy=50)	14 WF 320 + PL 24×3 (B.S.) (Fy=42)	14 WF 320 + PL 23×3 (B.S.) (Fy=42)	14 WF 426 (Fy=50)	14 WF 264 (Fy=50)	14 WF 264 (Fy=50)
El. 264'							
El. 253	▲ 14 WF 211 (Fy=50)	▲ 14 WF 550 (Fy=50)	▲ 14 WF 320 + PL 24×3⅝ (B.S.) (Fy=42)	▲ 14 WF 320 + PL 24×1⅜ (B.S.) (Fy=42)	▲ 14 WF 500 (Fy=50)	▲ 14 WF 370 (Fy=50)	▲ 14 WF 370 (Fy=50)
Top of base PL at El. 241'							
Base Plate	47×5⅛×3'-11"	73×9×6'-1"	88×11×7'-4"	88×11×7'-4"	68×8¼×5'-8	51×5⅝×4'-3"	57×6¼×4'-9"

* Provide proper splice pls., bolt holes & finished col. top for future columns. Use upper col. one size smaller except as shown.
▲ See detail on 10-JK4-3 and 4.
■ Splice 3" above slab. See note on 10-JK2-2.
● See detail on 10-JK2-30.

LICENSED PROFESSIONAL ENGINEER — LESLIE E. ROBERTSON — No. 34360 — UNIVERSITY OF THE STATE OF NEW YORK

DRAWN: SC
REVIEWED: E.L.

10-K1-234