WORTHINGTON, SKILLING, HELLE & JACKSON — Civil & Structural Engineers

PROJECT: THE WORLD TRADE CENTER | TITLE: COLUMN SCHEDULE | DATE: 5-15-67

REVISIONS
3-1-69
3-12-69
3-21-69
10-23-69
11-27-72

	K49-1			K49-4	K49-5	K49-6	
El. 332'							
El. 310'				*See Dwg. Book 13.		*See D.B. 13	
Street level							
El. 294'	14 WF 119 (Fy=50)			14 WF 320 + PL 23×2⅞ (B.S.) (Fy=42)	See D.B. 13	14 WF 264 (Fy=50)	
El. 284'							
El. 274'					14 WF 455 (Fy=50)	14 WF 314 (Fy=50)	
El. 264'	14 WF 193 (Fy=50)			14 WF 320 + PL 23×3 (B.S.) (Fy=42)			
El. 253				▲ 14 WF 320 + PL 24×3¼ (B.S.) (Fy=42)	▲ 14 WF 550 (Fy=50)	14 WF 398 (Fy=50)	
Top of base Pl at El. 241'							
Base Plate	41×4¼×3'-5"			88×11×7'-4"	69×8¼×5'-9"	57×6¼×4'-9"	

* Provide proper splice pls., bolt holes & finished col. top for future columns. Use upper col. one size smaller except as shown.
▲ See detail on 10-JK4-3 and 4.
■ Splice 3" above slab. See note on 10-JK2-2.
● See detail on 10-JK2-30.

LICENSED PROFESSIONAL ENGINEER — LESLIE E. ROBERTSON — No. 34360 — UNIVERSITY OF THE STATE OF NEW YORK

DRAWN S.C.
REVIEWED E.L.

10-K1-238