WORTHINGTON, SKILLING, HELLE & JACKSON Civil & Structural Engineers

PROJECT THE WORLD TRADE CENTER | TITLE COLUMN SCHEDULE | DATE 5-15-67

REVISIONS

12-17-68

	K54-51						
El. 332'							
El. 310'							
El. 294'	14 WF 158 (Fy=50)						
El. 284'							
El. 274'	Temp bracing 14 WF 228 (Fy=50) ▲						
El. 264'							
El. 253	14 WF 287 (Fy=50)						
Top of base Pl							
El. 243'-4"							
Base plate	41 × 4'4 × 3'-5"						

LICENSED PROFESSIONAL ENGINEER ★ LESLIE E. ROBERTSON ★ No. 34360 ★ UNIVERSITY OF THE STATE OF NEW YORK

✱ Provide proper splice pls., bolt holes & finished col. top for future columns. Use upper col. one size smaller except as shown.
▲ See detail on 10-JK4-3 and 4.
■ Splice 3" above slab. See note on 10-JK2-2.
● See detail on 10-JK2-30.

10-K1-248