WORTHINGTON, SKILLING, HELLE & JACKSON — Civil & Structural Engineers

PROJECT: THE WORLD TRADE CENTER | TITLE: COLUMN SCHEDULE | DATE: 5-15-67

REVISIONS

6-11-68

	KG1-8	KG1-9	KG1-10
El. 332'			
El. 310'			
Street			
El. 294'			
El. 284'	14WF103 (Fy=50)	14WF103 (Fy=50)	14WF111 (Fy=50)
El. 274'			
El. 264'	14WF150 (Fy=50)	14WF150 (Fy=50)	14WF237 (Fy=50)
El. 253	12 Girder	12 Girder	14WF237 ▲ (Fy=50)
Top of base Pl			
Base Plate			El. 243'-4" 39 × 4 × 3'-6"

* Provide proper splice pls., bolt holes & finished col. top for future columns. Use upper col. one size smaller except as shown.
▲ See detail on 10-JK4-3 and 4.
■ Splice 3" above slab. See note on 10-JK2-2.
● See detail on 10-JK2-30.

LICENSED PROFESSIONAL ENGINEER — LESLIE E. ROBERTSON — No. 34360 — UNIVERSITY OF THE STATE OF NEW YORK

10-K1-265