WORTHINGTON, SKILLING, HELLE & JACKSON — Civil & Structural Engineers

PROJECT: THE WORLD TRADE CENTER | TITLE: COLUMN SCHEDULE | DATE: 5-15-67

REVISIONS
6-7-68
6-28-68

	K73-13	K73-14	K73-15	K73-16	K73-17	K73-18	K73-19
El. 332'							
El. 310'							
El. 290'	14 WF 264 (Fy = 50)	14 WF 264 (Fy = 50)	14 WF 287 (Fy = 50)		14 WF 264 (Fy = 50)		14 WF 193 (Fy = 50)
El. 279'-3"	⊗ Temp. Bracing	⊗ Temp. Bracing	Temp. Bracing	14 WF 167 (Fy = 50)	14 WF 550 (Fy = 50)	14 WF 87 (Fy = 50)	14 WF 455 (Fy = 50)
El. 264'	20 x 12 II 2 PL 12 x 5 2 PL 10 x 4 (Fy = 50)	20 x 12 II 2 PL 12 x 5 2 PL 10 x 4 (Fy = 50)	14 WF 426 (Fy = 50)	14 WF 167 (Fy = 50)	14 WF 550 (Fy = 50)	14 WF 87 (Fy = 50)	14 WF 455 (Fy = 50)
Top of Base Pl.	El. 243'-4"	El. 243'-4"	El. 243'-4"	El. 243'-4"	El. 243'-4"	El. 243'-4"	El. 243'-4"
Base Plate	57 x 7¾ x 5'-1"	57 x 7¾ x 5'-0"	59 x 7 x 5'-5"	33 x 3⅛ x 2'-11"	53 x 6 x 4'-10"	22 x 2¾ x 2'-0"	51 x 5⅞ x 4'-6"

✱ Provide proper splice pls., bolt holes & finished col. top for future columns. Use upper col. one size smaller except as shown.
▲ See detail on 10-JK4-3 and 4.
■ Splice 3" above slab. See note on 10-JK2-2.
● See detail on 10-JK2-30.
⊗ Splice detail see 10-JK2-35A

10-K1-272

LICENSED PROFESSIONAL ENGINEER — LESLIE E. ROBERTSON — No. 34360 — UNIVERSITY OF THE STATE OF NEW YORK