WORTHINGTON, SKILLING, HELLE & JACKSON — Civil & Structural Engineers

PROJECT: THE WORLD TRADE CENTER | TITLE: COLUMN SCHEDULE | DATE: 5-15-67

REVISIONS
6-7-68
6-28-68

	K 74-19
El. 332'	
El. 310'	
El. 290'	14 WF 95 (Fy=50)
El. 279'3"	
El. 264'	14 WF 264 (Fy=50)
El. 253	▲ 14 WF 264 (Fy=50)
Top of Base Pl.	El. 243'-4"
Base Plate	38 x 3¾ x 3'-4"

✱ Provide proper splice pls., bolt holes & finished col. top for future columns. Use upper col. one size smaller except as shown.
▲ See detail on 10-JK4-3 and 4.
■ Splice 3" above slab. See note on 10-JK2-2.
● See detail on 10-JK2-30.

10-K1-275

LICENSED PROFESSIONAL ENGINEER — LESLIE E. ROBERTSON — No. 34360 — LICENSED TO PRACTICE IN THE STATE OF NEW YORK

C