WORTHINGTON, SKILLING, HELLE & JACKSON — Civil & Structural Engineers

PROJECT: THE WORLD TRADE CENTER | TITLE: COLUMN SCHEDULE | DATE: 12-17-68

REVISIONS

	K75-23	K75-54
El. 332'		
El. 310'		
El. 294'	14 WF 119 (Fy = 50)	14 WF 78 (Fy = 50)
El. 284'		
El. 274'	Temp. bracing; 14 WF 167 (Fy = 50)	
El. 264'	▲	
El. 253	14 WF 193 (Fy = 50)	
Top of base Pl	El. 243'-4"	
Base Plate	42 × 4 3/8 × 3'-6"	

* Provide proper splice pls., bolt holes & finished col. top for future columns. Use upper col. one size smaller except as shown.
▲ See detail on 10-JK4-3 and 4.
■ Splice 3" above slab. See note on 10-JK2-2.
● See detail on 10-JK2-30.

LICENSED PROFESSIONAL ENGINEER — LESLIE E. ROBERTSON — No. 34960 — UNIVERSITY OF THE STATE OF NEW YORK

10-K1-276A