WORTHINGTON, SKILLING, HELLE & JACKSON Civil & Structural Engineers

PROJECT THE WORLD TRADE CENTER | TITLE COLUMN SCHEDULE | DATE 5-15-67

REVISIONS
2-9-68
4-5-68

	J2-1	J2-2	J2-3	J2-4	J2-5	J2-6	J2-7
El. 332'							
El. 310'				* 14 WF 95 (Fy=50)	*	*	*
Street level				El. 301'-11" ▪			14 WF 136 (Fy=50)
El. 294'	14 WF 61 (Fy=42)	14 WF 87 (Fy=42)	14 WF 127 (Fy=50)		14 WF 136 (Fy=50)	14 WF 150 (Fy=50)	
El. 284'							Truss JT-2 See dwg. M-JJ-3
El. 274'							
El. 264'	14 WF 103 (Fy=50)	14 WF 142 (Fy=50)	14 WF 246 (Fy=50)		14 WF 264 (Fy=50)	14 WF 287 (Fy=50)	
El. 253	▲ 14 WF 103 (Fy=50)	▲ 14 WF 142 (Fy=50)	▲ 14 WF 246 (Fy=50)		▲ 14 WF 264 (Fy=50)	▲ 14 WF 287 (Fy=50)	14 WF 142 (Fy=50)
Top of base ■	El. 249'	El. 249'	El. 249'		El. 249'	El. 249'	El. 243'-6"
Base Plate	22 × 1⅝ × 2'-0"	28 × 2⅜ × 2'-6"	41 × 4⅛ × 3'-8"		41 × 4 × 3'-8"	43 × 4¾ × 3'-9"	33 × 3⅛ × 3'-0"

LICENSED PROFESSIONAL ENGINEER LESLIE E. ROBERTSON No. 34360 UNIVERSITY OF THE STATE OF NEW YORK

* Provide proper splice pls., bolt holes & finished col. top for future columns. Use upper col. one size smaller except as shown.
▲ See detail on 10-JK4-3 and 4.
■ Splice 3" above slab. See note on 10-JK2-2.
● See detail on 10-JK2-30.

10-JI-5