WORTHINGTON, SKILLING, HELLE & JACKSON — Civil & Structural Engineers

PROJECT: THE WORLD TRADE CENTER | TITLE: COLUMN SCHEDULE | DATE: 5-15-67

REVISIONS
5-1-68
9-4-68

	J2-18	J2-20	J2-22	J2-23	J2-23A	J2-24	J2-25
El. 332'							
	Top of ℄ Girder			Top of ℄ Girder			
El. 310'							
	14WF127 (Fy=50)	14WF228 (Fy=50)		℄ Girder 14WF264 (Fy=50)	Top of Girder 14WF150 (Fy=50)		14WF150 (Fy=50)
El. 290'							
	Port of Truss JK4					14WF127 (Fy=50)	
El. 271'				14WF264 (Fy=50)			
El. 264'			14WF87 (Fy=42)	14WF455 (Fy=50)		14WF314 (Fy=50)	14WF314 (Fy=50)
Top of base ℄			▲ 14WF87 (Fy=42)	▲ 14WF455 (Fy=50)		▲ 14WF314 (Fy=50)	▲ 14WF314 (Fy=50)
			El. 241'	El. 246'		El. 249'	El. 249'
Base Plate			24 x 2'8 x 2'-0"	55 x 6'2 x 5'-0"		45 x 4'8 x 4'-0"	45 x 4'8 x 4'-0"

✱ Provide proper splice pls., bolt holes & finished col. top for future columns. Use upper col. one size smaller except as shown.
▲ See detail on 10-JK4-3 and 4..
■ Splice 3" above slab. See note on 10-JK2-2.
● See detail on 10-JK2-30.

10-J1-8

LICENSED PROFESSIONAL ENGINEER LESLIE E. ROBERTSON No. 94800 UNIVERSITY OF THE STATE OF NEW YORK

B