WORTHINGTON, SKILLING, HELLE & JACKSON Civil & Structural Engineers

PROJECT THE WORLD TRADE CENTER | TITLE COLUMN SCHEDULE | DATE 5-15-67

REVISIONS
5-1-68
9-4-68
9-20-68

	J2-59	J2-60
El. 332'		
El. 310'		(*) 14 WF 78 (Fy = 50)
El. 294'		Top of Girder J2E
El. 284'		
El. 274'		
El. 264'		
El. 253		14 WF 287 (Fy 50)
Top of base PL	El. 253'-6"	
Base Plate	47 × 5 3/8 × 4'-2"	

* Provide proper splice pls., bolt holes & finished col. top for future columns. Use upper col. one size smaller except as shown.
▲ See detail on 10-JK4-3 and 4.
■ Splice 3" above slab. See note on 10-JK2-2.
● See detail on 10-JK2-30.

10-J1-11

LICENSED PROFESSIONAL ENGINEER LESLIE E. ROBERTSON No. 34260 UNIVERSITY OF THE STATE OF NEW YORK